

Mars Orbiter Laser Altimeter (MOLA): Experiment Summary after the First Year of Global Mapping of Mars

David E. Smith¹, Maria T. Zuber^{2,1}, Herbert V. Frey¹, James B. Garvin^{1,3}, James W. Head⁴, Duane O. Muhleman⁵, Gordon H. Pettengill^{2,6}, Roger J. Phillips⁷, Sean C. Solomon⁸, H. Jay Zwally⁹, W. Bruce Banerdt¹⁰, Thomas C. Duxbury¹⁰, Matthew P. Golombek¹⁰, Frank G. Lemoine¹, Gregory A. Neumann^{2,1}, David D. Rowlands¹, Oded Aharonson², Peter G. Ford⁶, Anton B. Ivanov^{5,10}, Catherine L. Johnson⁸, Patrick J. McGovern^{8,11}, James B. Abshire¹, Robert S. Afzal¹, and Xiaoli Sun¹

Abstract. The Mars Orbiter Laser Altimeter (MOLA), an instrument on the Mars Global Surveyor spacecraft, has measured the topography, surface roughness, and 1.064- μm reflectivity of Mars and the heights of volatile and dust clouds. This paper discusses the function of the MOLA instrument and the acquisition, processing, and correction of observations to produce global data sets. The altimeter measurements have been converted to both gridded and spherical harmonic models for the topography and shape of Mars that have vertical and radial accuracies of ~ 1 m with respect to the planet's center of mass. The current global topographic grid has a resolution of $1/64^\circ \times 1/32^\circ$, or $1 \times 2 \text{ km}^2$ at the equator. Reconstruction of the locations of incident laser pulses on the Martian surface appear to be at the 100-m spatial accuracy level and result in two orders of magnitude improvement in the global geodetic grid of Mars. Global maps of optical pulse width indicative of 100-m-scale surface roughness and 1.064- μm reflectivity with an accuracy of 5% have also been obtained.

Introduction and Investigation Objectives

The Mars Global Surveyor (MGS) spacecraft, launched November 7, 1996 by the National Aeronautics and Space Administration (NASA) and the Jet Propulsion Laboratory (JPL) of the California Institute of Technology, includes in

its payload an optical remote-sensing instrument, the Mars Orbiter Laser Altimeter (MOLA-2) [Zuber *et al.*, 1992]. The primary objectives of the MOLA investigation are to map globally the topography of Mars at a level suitable for geophysical, geological, and atmospheric circulation studies of Mars. Secondary objectives are to measure the heights of atmospheric reflections to better understand the three-dimensional structure of the Martian atmosphere; to measure 100-m-scale surface roughness of Mars to contribute to geological characterization of the surface and to assist in assessment of future potential landing sites; to measure the 1.064- μm surface reflectivity of Mars to contribute to knowledge of surface composition and seasonal changes; and to attempt to measure the time-varying topography of the Martian polar caps to contribute to understanding seasonal cycles.

With data collected in the capture orbit, aerobraking hiatus, science phasing, and the first 15 months of mapping orbits of the Mars Global Surveyor mission [Albee *et al.*,

¹Laboratory for Terrestrial Physics, NASA/Goddard Space Flight Center.

²Department of Earth, Atmospheric and Planetary Sciences, Massachusetts Institute of Technology.

³Now at: Office of Space Sciences, NASA Headquarters.

⁴Department of Geological Sciences, Brown University.

⁵Division of Geological and Planetary Sciences, California Institute of Technology.

⁶Center for Space Research, Massachusetts Institute of Technology.

⁷Department of Earth and Planetary Sciences, Washington University.

⁸Department of Terrestrial Magnetism, Carnegie Institution of Washington.

⁹Laboratory for Hydrospheric Processes, NASA/Goddard Space Flight Center.

¹⁰Jet Propulsion Laboratory.

¹¹Now at: Lunar and Planetary Institute.

2001], all MOLA objectives, with the exception of those relating to temporal changes, have been fully met, while those relating to temporal changes are currently being pursued. This report describes the function of the MOLA instrument, the measurement types, and the corrections and processing approach employed to produce the data products. In addition, the status and major accomplishments of the MOLA investigation are reviewed as of June 1, 2000, at which time the instrument was turned off for a two-month period surrounding solar conjunction.

Pre-MGS Observations

Martian Topography

Knowledge of the topography of Mars prior to Mars Global Surveyor was based on measurements obtained by the early Mariner and Viking spacecraft and on Earth-based radar measurements. These models and their errors are discussed in previous work [Davies *et al.*, 1992b; Esposito *et al.*, 1992; Zuber *et al.*, 1992; Smith and Zuber, 1996]. The most widely-used global topographic field prior to MGS was a digital elevation model (DEM) produced by the U.S. Geological Survey [Wu, 1991] that was based upon Earth-based radar [e.g., Pettengill *et al.*, 1971; Roth *et al.*, 1980; Downs *et al.*, 1982], Mariner 9 and Viking 1 and 2 radio occultations [e.g., Kliore *et al.*, 1965, 1972; Lindal *et al.*, 1979], stereo and photoclinometric observations from Mariner-9 and Viking imagery [Soderblom and Wenner, 1978; Wu and Peltier, 1984], and the Mariner-9 ultraviolet and infrared spectrometers [e.g., Hord, 1972; Conrath *et al.*, 1973]. The USGS DEM was referenced to an areoid derived from fitting atmospheric pressures obtained from Mariner-9 occultations [e.g., Kliore *et al.*, 1972, 1973] to a degree-4 gravity model [Lorell *et al.*, 1973]. The DEM has a spatial resolution of $1/64^\circ \times 1/64^\circ$ and is typically characterized by randomly-distributed vertical errors of ~ 1 km, though in some places deviations of over 5 km are observed [Smith and Zuber, 1998; Zuber *et al.*, 1998b; Smith *et al.*, 1999b].

As discussed later, the USGS DEM did poorly in matching the relative elevations of the Viking lander sites determined from atmospheric pressure measurements. Consequently, many pre-MGS Mars atmospheric studies, particularly dynamical analyses that used general circulation models with topography as a lower boundary condition [e.g., Pollack *et al.*, 1990], instead utilized the Mars Consortium topographic model [Kieffer *et al.*, 1981], which was based on orbital spectral data [e.g., Hord, 1972; Conrath *et al.*, 1973]. The Consortium data set was more successful in matching the lander elevations but suffered from a global-scale systematic error. In the Consortium Model the north pole is approximately 1 km higher than the south pole with respect

to the gravitational equipotential, whereas MOLA data have now shown that the south pole is 6 km higher than the north pole (see later discussion). This bias, along with other errors at shorter wavelengths, affected some past dynamical simulations of the circulation of the Martian atmosphere.

Smith and Zuber [1996] re-analyzed Viking and Mariner 9 occultation measurements to develop a topographic model of Mars that had poorer spatial resolution (~ 1300 km) but significantly improved vertical accuracy (~ 500 m) than the USGS DEM and in addition lacked the systematic errors of the Consortium model. The uncertainty of the occultation measurements in Smith and Zuber [1996] was due to combined uncertainties in orbital reconstruction (~ 400 m), atmospheric refraction (~ 300 m), timing errors in occultation measurements, and planetary ephemeris.

Earth-based radar range data have yielded regional measurements of elevation with a spatial resolution of $\sim 8 \times 80$ km² in the approximate latitude range $\pm 25^\circ$ during Mars opposition periods [Pettengill *et al.*, 1969, 1971, 1973; Goldstein *et al.*, 1970; Rogers *et al.*, 1970; Downs *et al.*, 1975, 1978; Roth *et al.*, 1980; Downs *et al.*, 1971, 1982; Harmon *et al.*, 1982; Harmon and Ostro, 1985; Esposito *et al.*, 1992]. Radar ranges are subject to ephemeris errors as well as errors due to solar plasma effects, for a total uncertainty of ~ 300 m in recent epochs. Selected radar observations in the vicinity of the Pathfinder landing site yielded an uncertainty of 100-200 m [Golombek *et al.*, 1997a]. Comparison of radii from occultations, which tend to measure topographic highs, and radar returns, which preferentially reflect from valley floors, yields a systematic difference of ~ 730 m [Smith and Zuber, 1996].

Geodetic Grid

Prior to Mars Global Surveyor, knowledge of locations on Mars on a planet-wide scale was based on spatial [Davies *et al.*, 1978; Davies and Katayama, 1982] and vertical [Wu and Schaefer, 1984] control networks derived from a variety of Mariner 9 and Viking Orbiter observations. While spatial errors were estimated to be < 3 km [Davies *et al.*, 1992b], actual errors in excess of 15 km were commonly observed [Smith *et al.*, 1999b; Duxbury, 2000]. Vertical errors were at a level comparable to the USGS DEM [Wu, 1991] (see above).

The best-known positions on Mars are the Viking and Pathfinder landing sites, because radio tracking has resulted in precise absolute positioning with respect to Mars' center of mass. While the position of Pathfinder based on radio tracking is known to a few tens of meters [Folkner *et al.*, 1997], reconstructed positions of the landing site with respect to images differ by 5 km [Duxbury, 1995; Zeitler and Oberst, 1999].

Macroscale Surface Roughness

Previous measurements of surface roughness of Mars are limited to Earth-based delay Doppler data at a spatial scale of several tens of kilometers [Rogers *et al.*, 1970; Pettengill *et al.*, 1973; Downs *et al.*, 1975, 1978; Harmon *et al.*, 1982; Harmon and Ostro, 1985; Simpson *et al.*, 1992]. There were no measurements of surface roughness at 100-m spatial scales prior to MGS.

Near-IR Reflectivity

Before Mars Global Surveyor, knowledge of the absolute reflectivity of the Martian surface in the 1- μm part of the spectrum was poorly known [Soderblom, 1992], with space-based observations limited to Phobos-2 ISM data for equatorial latitudes [Bibring *et al.*, 1990; Mustard *et al.*, 1993] and Hubble Space Telescope observations on a near-global scale with a spatial resolution of $\sim 1^\circ \text{ pixel}^{-1}$ [Bell *et al.*, 1999].

These observations indicated a bimodal distribution of reflectivity, with typical bright and dark values of 0.36 and 0.18, respectively [Bell *et al.*, 1999], and with noticeable changes occurring during the past 20 years due to variability in the atmosphere of Mars associated with the seasonal transport of dust.

Instrument Description and Operation

Background and Components

The Mars Orbiter Laser Altimeter (Plate 1) was designed by the Laser Remote Sensing Branch of the Laboratory for Terrestrial Physics of NASA's Goddard Space Flight Center, with support from Goddard's Engineering Systems Analysis Branch. The designation MOLA-2 refers to the instrument flown on Mars Global Surveyor, which is a descendant of the MOLA-1 instrument [Zuber *et al.*, 1992] that was carried aboard the ill-fated Mars Observer spacecraft.

Specifications of MOLA-2 are given in Table 1. The laser transmitter was built by McDonnell-Douglas Space Systems Division, and its detailed design and function are discussed by Afzal [1994]. The transmitter consists of a Q-switched, chromium- and neodymium-doped yttrium aluminum garnet (Cr:Nd:YAG) oscillator that is pumped by a 36-bar laser array. Each bar consists of about 80 aluminum, gallium arsenide (AlGaAs) laser diodes that optically excite the Cr:Nd:YAG material to produce lasing. The laser is pulsed at a 10-Hz rate controlled by the Q-switch and emits pulses with $\sim 8\text{-ns}$ full width at half the maximum amplitude (FWHM).

The design and function of MOLA receiver components are discussed elsewhere [Sun *et al.*, 1992; Ramos-Izquierdo *et al.*, 1994; Abshire *et al.*, 2000]. The optical system




Plate 1. The Mars Orbiter Laser Altimeter (MOLA). The laser is situated beneath the 0.5-m telescope, and the electronics and flight computer are in the black box on the left.

contains a 0.5-m-diameter, gold-coated beryllium telescope built by the Optical Corporation of America. In addition, the optical train includes a 2.2-nm-wide optical bandpass filter that rejects solar background and a silicon avalanche photodiode (SiAPD) detector that accumulates backscattered photons. The receiver also contains a time interval unit (TIU), which is a binary counter that records the number of clock cycles from the threshold crossings of the transmitted and returned pulses. The clock is an oven-heated crystal oscillator with a frequency of nearly 100 MHz ($99,996,311 \pm 2 \text{ Hz}$) and a short-term stability no worse than 10^{-10} . A charge-to-time converter (QT100) measures the time at which the pulse energy falls below the detection threshold. To improve range resolution the timing electronics includes interpolators for the transmitted and returned pulses. These allow determination of threshold crossing times to one-quarter of each 10-nsec clock cycle, yielding the effective 2.5-nsec period. The final major component of the MOLA receiver is an 80C86 computer that executes the flight software.

The Ranging Function

MOLA measures the round trip time of flight of individual laser pulses between the MGS nadir deck and the Martian surface or atmospheric layer. When the laser fires, a portion of the output laser energy is diverted to the SiAPD detector through a multimode optical fiber and starts the precision clock counter. Every 14 seconds, the laser fire time is compared to the MGS spacecraft time so that the location of the laser spot on the Martian surface can be reconstructed. The spacecraft time stamp has a resolution of 1/256 second.

Table 1. MOLA Instrument Specifications

Parameter	Specification
Mass	23.8 kg
Power consumption ^a	34.2 W
<i>Transmitter:</i>	
Laser type	diode pumped, Q-switched, Cr:Nd:YAG
Wavelength	1.064 μm
Pulse rate	10 Hz
Energy ^b	48 mJ pulse ⁻¹
Laser divergence	420 μrad
Pulse length	8 nsec
<i>Receiver:</i>	
Mirror	50-cm parabolic
Detector	silicon-avalanche photodiode
Field-of-view	850 μrad
<i>Electronics:</i>	
Microprocessor	80C86
TIU frequency	100 MHz
Filter channel widths	20, 60, 180, 540 nsec
Data rate	618 bits s ⁻¹ continuous
<i>Resolution:</i>	
Maximum ranging distance ^c	787 km
Range resolution	37.5 cm
Vertical accuracy ^d	1 m
Surface spot size ^e	168 m
Along-track shot spacing	300 m
Across-track shot spacing ^f	4 km

^a Includes replacement heat for temperature control^b At arrival at Mars; degrades with time^c Hardware limited^d Includes radial orbit error^e In 400-km-elevation mapping orbit^f Average at equator; varies with $\cos(\text{latitude})$

The backscattered pulse is detected within a range gate, which represents a period of time during which the return is expected. The purpose of the range gate is to minimize noise due to direct or surface backscattered solar photons at the laser wavelength. MOLA's range gate is adaptable in

width, but because of strong signal return it almost always operates at its minimum that corresponds to 20 km in range. The telescope focuses the laser photons scattered by terrain or clouds onto the SiAPD detector. The detector outputs a voltage proportional to the rate of returning photons that have been backscattered from the Martian surface or atmosphere. When this voltage exceeds a noise threshold, counts are latched by the TIU. The clock stops, and the round-trip time of flight is recorded. The TIU also measures time at which the pulse energy falls below the detection threshold on its trailing edge, which, when differenced with the leading edge detection, provides a measure of the pulse width, discussed later.

To avoid false triggers due to solar photons at the laser wavelength that have been backscattered from Mars, the noise threshold in the receiver electronics is continuously adjusted by software, based on statistics from the past 14 seconds worth of returns [McGarry *et al.*, 1991]. In practice, MOLA minimizes the probability of false alarms P_{fa} while maximizing the probability of detection P_{det} according to the relationship [Zuber *et al.*, 1992; Abshire *et al.*, 2000]

$$P_{meas} = P_{det} (1 - P_{fa}), \quad (1)$$

where P_{meas} is the probability of making a successful range measurement. The software is implemented such that a constant false alarm rate of 1% on all four matched filter channels (*cf.* Table 2) is maintained. MOLA's adaptive noise threshold allows detection of both strong ground returns and weak atmospheric returns without special modification of the receiver by the user. The receiver design and flight software are in contrast to the designs on the Clementine [Smith *et al.*, 1997] and Near Earth Asteroid Rendezvous (NEAR) Shoemaker [Cole *et al.*, 1997] laser ranging devices, in which threshold settings require a command upload for adjustment.

By interpolating the spacecraft orbital trajectory to the time of the laser measurement, the distance between the spacecraft and the Martian center of mass is obtained. The range R_{Mars} from MGS to the Martian surface is related to the time of flight t_{opt} of the optical pulse by

$$R_{Mars} = \frac{ct_{opt}}{2}, \quad (2)$$

where c is the vacuum speed of light. The vector difference between the radial distance to the spacecraft from the planetary center of mass and the range to the surface provides the radius of Mars at the location of the laser spot on the surface. Equation 2 neglects the effect of the atmospheric path delay, which is only a centimeter on Mars due to the thin Martian atmosphere. In the MGS mapping orbit, the instrument's sampling rate combined with the laser beam divergence (*cf.*

Table 2. MOLA Matched Filter Characteristics

Characteristic	1	2	3	4
Description	smooth	moderate	rough	clouds
Channel width, nsec	20	60	180	540
Terrain height variation within footprint, m	3	9	27	81
Footprint-scale surface slope, deg	1.0	2.9	8.6	24.2

Table 1) results in a surface spot size of ~ 168 m with shot-to-shot spacings of ~ 300 m. The precision of MOLA range measurements approaches the limiting resolution of 37.5 cm on smooth level surfaces and may increase up to ~ 10 m on 30° -slopes [Gardner, 1992; Abshire *et al.*, 2000].

Footprint-Scale Slopes and Surface Roughness

The width of MOLA's backscattered laser pulse provides a measure of the target height variance or relief, which can be interpreted as footprint-scale slope or root mean square (RMS) roughness. Pulse width can be measured in two ways from MOLA, and the results represent the first quantitative measurements of the local vertical structure of the Martian surface and atmosphere at ~ 160 -m length scales.

A coarse roughness estimate can be derived from the instrument's matched filters (Table 2). After passing through the SiAPD detector, MOLA's returned signal is amplified and subsequently passed through a bank of four five-pole Bessel filters that sample the voltage output in parallel to detect pulses that have been spread in time by RMS variance in the height of the target within the sampled footprint. These matched filters increase the likelihood of detection and in addition provide some information about target characteristics. The instrument records only the narrowest (with respect to time) channel that triggers, identifying the filter that most closely matches the width of the return. The matched filters provide a one-in-four bin measure of within-footprint variance.

A more refined measure is obtained by using the difference in the times at which the leading and trailing edges of the returned pulse cross the detection threshold, which is a measure of the optical pulse width. The pulse spreading contains contributions due to both footprint-scale slopes and roughness within the footprint. If it is assumed that pulse

spreading is solely a consequence of footprint-scale slope θ , then the relationship between slope and the width σ_r of the backscattered pulse is [Gardner, 1982]

$$\sigma_r^2 = (\sigma_x^2 + \sigma_f^2) + \frac{4R_{\text{Mars}}^2}{c^2} [\tan^4(\gamma) + \tan^2(\gamma) \tan^2(\theta)] \quad (3)$$

where σ_x is the transmitted laser pulse width, σ_f is the receiver impulse response, and γ is the laser divergence angle (*i.e.*, the half angle at the $1/e^{1/2}$ intensity point). The first term inside the brackets in Equation 3 accounts for the effect of laser beam curvature and can often be neglected since $\gamma \ll \theta$.

In most areas of Mars, however, the spreading of the optical pulse is dominated by roughness rather than local slope [Garvin *et al.*, 1999]. In such cases the width of the unsaturated backscattered pulses above the detection threshold can be used to derive roughness by correcting the returned pulse for local slopes determined from MOLA ranging [Garvin *et al.*, 1999]. This approach has been verified from study of returned pulse widths measured for terrestrial desert surfaces by the Shuttle Laser Altimeter (SLA) [Garvin *et al.*, 1998], which has a receiver design nearly identical to that of MOLA. Note that the pulse width parameter is an RMS value and does not fully represent the possible local extremes of small-scale roughness.

During the initial months of the MGS global mapping mission (March 1999 to late June 1999), the detection threshold settings within the MOLA instrument were set based on strong surface signals that saturated the detector. As a consequence, resulting measurements of pulse width and pulse energy (discussed next) were unusable due to corruption of their absolute magnitudes. By adjusting the threshold settings within MOLA on July 2, 1999, the percentage of saturated shots decreased and more robust measurements of pulse width became possible. Specifically, the threshold of channel 1 was raised, thereby reducing the probability of false triggers, while allowing more triggers to occur on higher channels. Following this change, the total percentage of false triggers has consistently been 1.25%. Since that time, the behavior of the calibrated optical pulse width parameter has been tracked, and is reproducible at the 10% to 20% level in places where there are abundant crossovers, such as in high-latitude regions.

Clouds

MOLA is also an atmospheric lidar, having provided the first quantitative characterization of the three-dimensional distribution of cloud fronts on Mars [Zuber *et al.*, 1998c; G. A. Neumann and Zuber, 2001; Pettengill and Ford, 2000],

both during the day and at night. Clouds are diffuse targets, but MOLA's matched filters (Table 2) and the instrument's adaptive detection threshold enhance their probability of detection.

For each pulse, MOLA's leading edge detector will trigger only once. If an atmospheric reflector with sufficient opacity and backscatter cross-section is encountered within MOLA's range gate, an atmospheric reflection will register. In MOLA's nominal operating mode, only clouds within the minimum range gate width (20 km) of the surface will trigger. The center point of the range gate is determined autonomously on the basis of the last 14 seconds worth of laser ranges [McGarry *et al.*, 1991]. For particularly dense clouds, such as the polar hoods over the winter pole, the instrument will sometimes lose lock on the surface and track clouds [Zuber *et al.*, 1998c; G. A. Neumann and Zuber, 2001].

MOLA range data are classified semi-automatically into ground and non-ground returns using a stochastic tracking algorithm, followed by manual editing [G. A. Neumann and Zuber, 2001]. If three or more non-ground triggers have occurred within a 0.5-s window, or 6 or more in a 6-s window (~ 20 km on the ground), a non-ground trigger is deemed to be a reflective "cloud," since the probability of such groups occurring by chance is less than 0.001%. Non-reflective clouds also occur and are characterized by groups of 2 or more shots in a 2-s window that do not trigger on any channel, or by average reflectivity-transmittance product (as described in the next section) being less than 0.02 for the same window. Reflective clouds on channels 1 and 2, with photons arriving within 20 or 60 ns (Table 2), are "sharp", while returns from channels 3 and 4 are "diffuse". "Sharp" cloud fronts have mainly been observed on the flanks of the southern polar cap [G. A. Neumann and Zuber, 2001].

Surface Reflectivity

The reflectivity r_{Mars} of the Martian surface at the laser wavelength is determined from the ratio of received to transmitted laser energy, corrected for distance and the Lambert reflection law. The energy of the outgoing pulse E_{trans} is sampled with an optical fiber that measures $\sim 95\%$ of the outgoing pulse cross-section, which consists of a charge-to-time converter and an 8-bit counter. The energy E_{rec} of the received pulse is derived from the area under the curve representing the best estimate of the returned pulse shape, which is measured by a second energy monitor. The energy of the pulse (in millijoules) and the pulse width w (in nanoseconds, defined as the full width at half the maximum amplitude), are related by the expression [Abshire *et al.*, 2000]

$$w = 326.62 E_{\text{trans}}^{-0.95} \quad (4)$$

The relationship between r_{Mars} and the ratio of the received/transmitted pulse energies is expressed by re-arranging the laser link equation as [Abshire *et al.*, 2000]

$$r_{\text{Mars}} = \frac{E_{\text{rec}}}{E_{\text{trans}}} \cdot \frac{t_{\text{atm}}^2}{\tau_r} \cdot \frac{\pi r_{\text{Mars}}^2}{A_r}, \quad (5)$$

where t_{atm} is the one-way atmospheric transmissivity, τ_r is the optical transmission of the receiver, and A_r is the aperture area of the receiving telescope. The accuracy of the reflectivity measurement after calibration is $\sim 5\%$. In practice, r_{Mars} contains contributions from the reflectivity of the terrain, r_{terr} , and the opacity of the atmosphere. If independent atmospheric opacity information is available, such as from the MGS Thermal Emission Spectrometer (TES) [e.g., Smith *et al.*, 2000], then the reflectivity of the surface can be obtained using Beer's law

$$r_{\text{terr}} = \frac{r_{\text{Mars}} \cdot e^{2\tau_{\text{atm}}}}{Op}, \quad (6)$$

where Op is the returned signal enhancement due to the opposition effect [Hapke *et al.*, 1998]. In using TES data, a scaling factor must be applied to correct the TES 9- μm dust opacity to the MOLA wavelength of 1.064 μm . The scaling of dust opacity in the infrared to the MOLA wavelength may contribute up to 20% of the error in the measured surface reflectivity [Ivanov and Muhleman, 1998].

Atmospheric Opacity

If there is an independent estimate of the reflectivity of terrain in areas where MOLA has ranged, then the MOLA reflectivity measurement can be used to provide an estimate of the 1.064- μm opacity τ_{atm} of the Martian atmosphere. The opacity can be expressed [Ivanov and Muhleman, 1998]

$$\tau_{\text{atm}} = -\frac{1}{2} \ln \left(\frac{r_{\text{Mars}}}{r_{\text{terr}}} \right). \quad (7)$$

In a proof-of-concept study during the MGS science phasing orbits, radiometrically-calibrated Viking color MDIMs [Eliason *et al.*, 1992] were used to correct for the reflectivity of the Martian surface. Since the wavelength of the Viking red filter is 0.55 to 0.70 μm , a scaling factor was used to convert to 1.064 μm [Ivanov and Muhleman, 1998].

Data Products

Data from MOLA are transmitted from MGS to stations of the NASA Deep Space Network, after which they are transmitted to NAA/GSFC, where all processing occurs. Raw MOLA Experiment Data Records (EDRs) are processed into Precision Experiment Data Records (PEDRs)

that contain profiles of all MOLA's measured and derived parameters, as well as the value of the areoid [Smith *et al.*, 1999a] at each shot location and a flag to indicate ground returns.

The profile data are assembled into Experiment Gridded Data Products (EGDRs) of a resolution that depends on data density and distribution. The MOLA team is contractually obligated to submit for archiving grids developed from data in hand after 30 days of global mapping and at the end of the MGS mission. However, the team has so far submitted and intends to continue to submit to the NASA Planetary Data System (PDS) grids of progressively increasing resolution and vertical accuracy on a 3-month schedule.

Differences Between MOLA-1 and MOLA-2

In rebuilding the instrument (MOLA-2) for MGS, minor changes were implemented in order to reduce risk, several of which coincidentally also increased performance. The laser power-on sequence was modified in order to mitigate a turn-on transient and protect optical coatings from damage. Improvements in the laser diode fabrication process allowed selection of diodes that provided maximum pulse energy over a broader temperature range than MOLA-1. The sampling of the start pulse energy was re-designed in order to measure 95% cross-sectional area of the output laser beam. This change enabled the $1.064\text{-}\mu\text{m}$ measure of surface reflectivity to improve from 20% in MOLA-1 to approximately 5% in MOLA-2. A trailing-edge detector was added so that the returned pulse width could be measured independently and with much finer resolution than with matched filters (Table 2). Finally, three delay lines were added to the TIU so that a clock cycle could be encoded at quarter-cycle intervals. This addition improved the range resolution from 1.5 m to 37.5 cm.

Geodetic Corrections

Orbit Determination

Subtraction of the range to the surface from the MGS orbit, allowing for off-nadir pointing, yields measurements of Martian radius in a center-of-mass reference frame. The surface topography h_{shot} with respect to the gravitational geopotential at the shot point can be obtained from

$$h_{\text{shot}} = R_{\text{shot}} - R_{\text{areoid}}, \quad (8)$$

where R_{shot} is planetary radius at the shot point with respect to Mars' center of mass determined from MOLA, and R_{areoid} is the radius of the areoid determined from the gravity field [Smith *et al.*, 1999a].

Precision spacecraft orbits were determined using the NASA/GSFC GEODYN/SOLVE orbit determination and parameter estimation system of programs [Rowlands *et al.*, 1993; McCarthy *et al.*, 1994]. GEODYN numerically integrates the spacecraft Cartesian state and force-model partial derivatives by employing a high order Cowell predictor-corrector model. The force modeling includes a spherical harmonic representation of the Martian gravity field, as well as point mass representations for the Sun and other planets (except Pluto). Solar radiation pressure, measurement and timing biases, and tracking station coordinates can also be also estimated. The accuracy of the laser spot location in latitude and longitude is limited by the knowledge of the spacecraft pointing at a nominal level of 1 to 3 mrad (400 to 2000 m on the surface, depending on the spacecraft altitude) and absolute spacecraft position uncertainties of order 100 m.

Altimetric Crossovers

Errors in the gravity field model used in the computation of spacecraft orbits cause geographically-correlated errors [Tapley and Rosborough, 1985] in spacecraft position that cannot be removed by including additional tracking data. Such errors have been observed for Earth-orbiting spacecraft as well as for MGS [Lemoine *et al.*, 1999]. In the case of MGS, high-precision gravity models developed at both JPL and NASA/GSFC [Smith *et al.*, 1999a; Lemoine *et al.*, 2001; Yuan *et al.*, 2001] show internal accuracies for the radial position of MGS at the sub-meter level. But orbit overlap estimates do not take into account systematic errors. Comparison of these Doppler-only orbits with MOLA ranges at over 24 million altimeter crossover locations show radial errors at the 3- to 5-m level.

Orbital crossover analysis is a method for using altimetry as an observation type for non-topographic purposes. Crossovers are locations on the surface of a planet where the groundtrack of an orbit crosses over a previous track. At these locations a measure of the radius of the planet is obtainable from both orbits. The crossover observations are sensitive to orbital errors and can therefore be used as an observation of the spacecraft radial position in the orbit determination process [Shum *et al.*, 1990]. Thus, crossovers can be combined with the Doppler tracking of the spacecraft to improve the orbit and, simultaneously, to estimate changes in the topography or shape of the planet due to seasonal mass re-distribution between the polar caps and atmosphere, tides, and other effects.

Experience with the use of crossovers in satellite geodesy includes Earth-orbiting radar altimeter satellites, such as TOPEX [Marshall *et al.*, 1995]. Crossovers have been used for the first time on a planetary spacecraft for MGS

and have resulted in demonstrated improvements in radial, along-track, and across-track orbit components [Rowlands *et al.*, 1999; Neumann *et al.*, 2001].

Geodetic Conventions

Mars Global Surveyor utilizes a spacecraft-fixed (XYZ) coordinate system along whose axes the spacecraft Inertial Measurement Units (IMU) are aligned to measure the spacecraft attitude, and thus the inertial pointing of the science instruments. An instrument coordinate system is used to define the mounting of the instrument with respect to the spacecraft-fixed system. The Earth Mean Equator and Vernal Equinox 2000 (*i.e.*, $J2000$) is used as the standard inertial reference system to describe the spacecraft trajectory, planetary body ephemerides, star positions, inertial orientations of planetary body-fixed coordinate systems, inertial spacecraft attitude, and inertial instrument pointing. A series of matrix transformations relate the instrument-fixed coordinates to inertial $J2000$ coordinates. All calculations for topography are done in a mass-centered, areocentric coordinate reference system, with longitude defined as positive eastward with the prime meridian defined according to Davies *et al.* [1992a]. Geodetic constants assumed in the MOLA investigation are based on the IAU91 reference system [Davies *et al.*, 1992a] and are given in Table 3. The gravity field of Mars is being continuously refined through the efforts of the MGS Radio Science Team [Tyler *et al.*, 2001]. The areoid in this analysis is based on gravity model mgm0964c20a [Lemoine *et al.*, 1999; Smith *et al.*, 1999a; Zuber *et al.*, 2000a], while orbits have recently been re-computed with an updated version of the field, mgm1004d [Lemoine *et al.*, 2001].

Reference Surface

Zero elevation on Mars from MOLA is defined as the equipotential surface (gravitational plus rotational) whose average value at the equator is equal to the mean radius as determined by MOLA (*cf.* Table 4). The planetary radius and a gravity model derived from MGS Doppler tracking data [Lemoine *et al.*, 2001] with the IAU91 coordinate system parameters for Mars [Davies *et al.*, 1992a] collectively provided the geopotential of Mars mean equatorial radius. This equipotential surface was then extended to all latitudes as the zero-level reference for topography.

Instrument Calibration

Pre-Launch Characterization

MOLA-2 was calibrated prior to its launch on MGS by characterizing its performance over the complete range of




Figure 1. MOLA oscillator frequency and range drift during the MGS mapping orbit through May 2000.

anticipated operating conditions. The calibration included a full flow-through system test that featured lasing to a remote target. The amount of energy emitted by a laser at the desired wavelength is a strong function of temperature [*cf.* Byer, 1988] such that the maximum energy output occurs within a temperature range specific to the particular laser. Laser operation within a relatively narrow temperature range allows performance near the maximum energy. Thus, an important aspect of pre-launch testing was assessment of the temperature dependence of the laser output energy that was accomplished by sampling of the output beam.

Timing and Range Drift

During flight, the MOLA-2 oscillator frequency is compared regularly with the MGS spacecraft clock through the spacecraft RF transmitter carrier frequency. The purpose is to monitor oscillator drift that affects ranging accuracy. Figure 1 shows that during the MGS mapping orbit through May 2000 range drift of up to 23 cm was observed and corrected. By performing this comparison in combination with spacecraft pointing information provided by the quaternions, it is possible to determine the along-track position of each laser footprint on the Martian surface.

Laser Performance

The post-launch performance of the MOLA laser is consistent with the most optimistic expectations based on pre-launch testing. The performance is particularly significant considering that the instrument was operated in an unintended fashion – outside its nominal operating temperature range, and switched on and off rather than run continuously – during the MGS aerobraking hiatus and science phasing orbit periods [Albee *et al.*, 2001]. During the combined orbit phases MOLA exhibited an $\sim 99\%$ rate of valid returns from

Table 3. Mars Constants Used by MOLA

Parameter/Model	Value	Units	Reference	Comments
Reference System			^a	IAU91
Pole, 2000 RA	5.544579446831762E+00	radians	^a	J2000
Pole, 2000 Dec	9.230348427839985E-01	radians	^a	J2000
Rotation rate	7.088218081252292E-05	radians s ⁻¹	^a	constant
Origin, Ω_o	176.868+350.8919830*d	degrees	^a	
Gravity model	mgm0964c20		^b	areoid
	mgm1004cd		^d	MGS orbit
GM	0.42828371300166E+14	m ³ sec ⁻²	^d	mgm0964c20a
	0.42828371901284E+14	m ³ sec ⁻²	^d	mgm1004d
Mean equatorial radius	3396000	m	^c	topography model
	3397000	m	^d	gravity models
Planetary ephemeris	DE403		^e	
Coordinate system	planetocentric			east positive

^a[Davies *et al.*, 1992a]^b[Smith *et al.*, 1999a]^c[Smith *et al.*, 1999b]^d[Lemoine *et al.*, 2001]^e[Standish *et al.*, 1995]

the surface and atmosphere. When MOLA-2 was turned off prior to Mars solar conjunction in June 2000, the laser had accumulated over 390 million pulses, making it by far the longest-lived laser ranging instrument that has so far flown in space. By comparison, the Clementine laser accumulated 647,000 pulses (of which 81% of the returns were noise hits) [Smith *et al.*, 1997] and the Shuttle Laser Altimeter, an Earth-orbiting instrument built with MOLA spares, expended about 3 million pulses in two shuttle flights [Garvin *et al.*, 1998]. The NEAR Shoemaker Laser Rangefinder [Zuber *et al.*, 1997] accumulated approximately 11 million pulses during the one-year mapping mission of asteroid 433 Eros [Zuber *et al.*, 2000b].

Even in the absence of mechanical and electrical problems and with nominal operating conditions, lasers of all kinds experience a degradation in performance with time. For solid-state lasers like that in MOLA, laser energy is expected to decrease with usage due to failure of laser diodes [Afzal, 1994]. As illustrated in Figure 2, the MOLA laser has experienced several discrete decreases in the output energy during its operation in Martian orbit. Decreasing laser energy was anticipated and factored in to MOLA's design, though prior to MOLA-2 it was expected that energy would fall off as a smooth exponential fashion rather than in dis-

crete steps [Zuber *et al.*, 1992; Afzal, 1994]. The laser energy drops have occurred on approximately 60-day intervals during MOLA's continuous operation in the mapping orbit. The most likely cause of the energy decreases is the failure of individual diode bars, resulting in an ~ 4 -mJ energy drop per failure. Monotonic increases and decreases in energy are due to temperature variations associated with the changing distance of Mars to the Sun during the Martian year.

On day 432 of 1999 (March 7, 2000) the MOLA laser briefly experienced an unusual variation in energy output due to significant unexpected variations in the temperature of the MGS nadir deck. These temperature excursions were associated with the first execution of the fixed high-gain mapping sequence [Albee *et al.*, 2001] that was implemented to allow occultation measurements during a period when the MGS high-gain antenna obstruction prevented continuous mapping of the Martian surface. Subsequent to this event the MGS mapping sequence was modified to prevent further occurrences of this kind.

Under normal operating conditions, MOLA-2 is expected to perform with full capability as long as performance exceeds 10 mJ in daytime and 5 mJ at nighttime.




Figure 2. Daily averages of MOLA laser energy (in mJ) during the MGS mapping orbit. Time is given as day of 1999, and values greater than 365 correspond to the year 2000.

MGS Mission Phases and MOLA Data Collection

Mars Global Surveyor successfully inserted into Martian orbit on September 11, 1997. The capture orbit was elliptical and near-polar in inclination, with an initial period of 45 hours. The capture orbit was changed into a circular mapping orbit by aerobraking, utilizing repeated passes through the upper atmosphere of Mars near orbital periapsis to remove energy from the spacecraft orbit via drag on the solar panels. Aerobraking reduces the apoapsis height, eccentricity, and period. MOLA was unable to range to the surface while the MGS spacecraft was in aerobraking configuration. On September 15, 1999, prior to the initiation of aerobraking, periapse 3 of the capture orbit was designated as a period of instrument check out. During this orbit MOLA collected its first data from Mars. The instrument sampled the Martian surface for a total of 21 minutes as the spacecraft passed through altitudes less than 787 km, MOLA's hardware-defined maximum distance ranging limit. The ranging success rate during Pass 3 was 99.8% [Smith *et al.*, 1998]; there were no missed shots and only about 20 false detections.

From October 14 to November 6, 1997, the periapsis height of MGS was raised out of the atmosphere to 175 km. Aerobraking was suspended to analyze the effect of the dynamic pressures experienced during atmospheric passes on one of the solar panels that was damaged when deployed shortly after launch. During these aerobraking hiatus orbits, seventeen more MOLA profiles were collected [cf. Smith *et al.*, 1998]. The orbital period of the aerobraking hiatus orbits was approximately 35 hours, and the length of the

ranging pass was approximately 22.5 minutes.

MGS implemented the science phasing orbits (SPO) between April and September, 1998 [Albee *et al.*, 1998]. These science data-collecting orbits were undertaken to allow the originally planned 2:00 AM/2:00 PM equator-crossing times to be achieved in the MGS circular mapping orbit. The SPO had a period of 11 hours 37 minutes and an approximate periapsis altitude of 170 km that allowed about 25 minutes of ranging each orbit. During SPO-1 and -2, with the numbers corresponding, respectively, to periods before and after solar conjunction, MOLA collected over two million elevation measurements of Mars' northern hemisphere. The SPO orbits lasted until mid-September 1998, but MOLA turned off on August 1 to avoid cycling the laser on and off, a usage which had not been planned for in the instrument design.

MOLA began continuous mapping of Mars in the near-polar, circular MGS mapping orbit on February 28, 1999. The instrument has ranged continuously to Mars at a 10-Hz rate until June, 1999 except for a 2-week period in April 1999 when all instruments were shut off to investigate an obstruction of the MGS High Gain Antenna. In June 1999 MOLA was shut off for a two-month period around solar conjunction, when solar plasma induced a level of noise in the MGS X-band tracking data that translated to unacceptable errors in the spacecraft orbit and hence MOLA topographic accuracy.

Global Topographic Model

Data and Resolution

The topographic model, shown in Plate 2, is based on 333,689,830 MOLA ground shots. Data were corrected for spacecraft attitude, for pointing angles $< 6^\circ$ except where off-nadir ranging was performed to cover the north and south poles in areas not routinely sampled due to the 92.8° inclination of the MGS orbit. To derive location coordinates and median heights, all ground shots were projected and binned on a $1/64^\circ$ latitude \times $1/32^\circ$ longitude global grid. The resolution of the global grid is currently $\sim 1 \times 2 \text{ km}^2$ at the equator, with longitudinal spacing decreasing with the cosine of latitude. More than half of the bins contained at least one observation, and usually more than three, while the remainder were interpolated by minimum-curvature-under-tension [Smith and Wessel, 1990]. Planetary radii were then projected and similarly binned, and a spherical harmonic expansion was subsequently fit to the data. The spherical harmonic solution of mass-center radii, R_{Mars} , converted to geopoten-




Figure 3. Histogram of orbit residuals at over 48 million altimetric crossover points. The least median of squares (LMS) misfit of 0.96 m is a measure of the accuracy of the global topographic model in Plate 2. No attempt has been made here to remove any time-varying height effect due to sublimation and deposition of CO₂ on the polar caps.

tial elevation h_{Mars} by equation 8, takes the form

$$h_{\text{Mars}}(\phi, \lambda) = \sum_{l=1}^N \sum_{m=0}^l P_{l,m}(\sin \phi) \cdot [C_{l,m} \cos(m\lambda) + S_{l,m} \sin(m\lambda)] \quad (9)$$

where ϕ and λ are the areocentric latitude and longitude of the surface, $P_{l,m}$ are the normalized associated Legendre functions of degree l and azimuthal order m , $C_{l,m}$ and $S_{l,m}$ are the normalized spherical harmonic coefficients with units given in meters, and N is the maximum degree representing the size (or resolution) of the field. The C and S coefficients provide information on the distribution of global topography. The current spherical harmonic model is to degree and order 1152 and has a spatial resolution of ~ 9 km.

The estimate of global topographic accuracy includes contributions from radial orbit error (0.85 m RMS) [Lemoine *et al.*, 2001], instrument error (3 m RMS) [Abshire *et al.*, 2000], and areoid error (± 5 m RMS) [Lemoine *et al.*, 1999, 2001; Smith *et al.*, 1999a]. Figure 3 demonstrates that inclusion of MOLA altimetric crossovers has reduced the misfit of topography at crossover locations to ± 0.96 m [Neumann *et al.*, 2001], and to first order this misfit represents the accuracy of the topographic model.

Table 4. MOLA Geodetic Parameters

Parameter	Value/Uncertainty
<i>Geodetic Shape:</i>	
Mean radius	3389508 ± 3 m
Mean equatorial radius	3396200 ± 160 m
North polar radius	3376189 ± 50 m
South polar radius	3382580 ± 50 m
<i>Triaxial ellipsoid:</i>	
a	3398627 m
b	3393760 m
c	3376200 m
1/flattening	169.8 ± 1.0
<i>Directions of principal axes:</i>	
a	1.0°N, 72.45°E
b	0.0°N, 324.4°E
c	89.0°N, 252.4°E
<i>Ellipsoid offset of COF from COM:</i>	
Δx	-233 m
Δy	-1428 m
Δz	-2986 m

Fundamental Parameters of Shape

Basic parameters of the shape of Mars are given in Table 4. Mars has a mean radius with respect to its center of mass of 3389508 ± 3 m, but the global distribution of radii shows considerable variability. The difference of ~ 20 km between the polar and equatorial radii indicates that the largest contribution to the shape is the planetary flattening, which is due primarily to the rotation of Mars. There is an approximately 5% contribution [Folkner *et al.*, 1997; Zuber and Smith, 1997] to the flattening from the Tharsis province, which is situated near the equator. The flattening of $1/169.8$ is significantly less than the value of $1/154.4$ [Bills and Ferrari, 1978] and slightly less than the ellipsoidal value of $1/166.53$ [Smith and Zuber, 1996] that have been used in previous geophysical analyses.

Subtracting the gravitational potential or areoid [Smith *et al.*, 1999a; Lemoine *et al.*, 2001] from planetary radii measurements gives elevations in terms of geopotential topography, which eliminates the contribution due to rotation and accentuates other long-wavelength components of the shape. Table 5 illustrates that the dynamic range of geopotential topography on Mars is 29.5 km, the largest of the ter-




Figure 4. Hypsograms of surface elevation with respect to Mars' center of mass (solid line) and with the degree-one terms omitted (dotted line).

restrial planets. The major topographic excursions are due to large impact basins and shield volcanoes. Mars' thick elastic lithosphere [Turcotte *et al.*, 1981; Banerdt *et al.*, 1982; Comer *et al.*, 1985; Sleep and Phillips, 1985; Banerdt *et al.*, 1992] allows such large surface loads to be maintained (see below).

Best-fit Ellipsoid

A commonly-used measure of the planetary shape is the reference ellipsoid. Parameters of the best-fit ellipsoid, calculated with respect to a coordinate system with origin at Mars' center of mass (COM), are given in Table 4. The ellipsoid is displaced from the COM by -2986 m along the z -axis, and represents an offset between the COM and the planet's geometric center (center of figure; COF) along the polar axis. The sign of the offset indicates that the south pole has a higher elevation than the north pole (by ~ 6.4 km, including relief of the ice caps). The ellipsoid is also displaced by ~ 1428 m along the y -axis in the direction of the Tharsis topographic rise.

Geodetic Grid

MOLA data have been used to re-define the geodetic grid of Mars and have provided up to two orders of magnitude improvement in knowledge of the absolute locations of latitude and longitude and three orders of magnitude improvement in knowledge of radius over all previous control point networks [e.g., Davies *et al.*, 1992b]. Using geolocated positions of MOLA spots on the Martian surface [Rowlands

et al., 1999; Smith *et al.*, 1999b], the locations sampled by MOLA are now known to one MOLA footprint or approximately ± 100 m with respect to Mars' center of mass. Vertical positions are known to the accuracy of the global topographic model, or about 1 m.

Effort is currently underway [Duxbury, 2000] to re-locate into the MOLA coordinate system the Mars Medium-resolution (231-m pixel^{-1}) Mosaicked Digital Image Models (MDIMs) [Davies *et al.*, 1992b] derived from Viking images. This process utilizes MOLA Geodetic Altimetry (MOGAL) files [Duxbury, 2000] in which MDIM's are brought into alignment with control-point features, such as craters, sampled in MOLA PEDRs.

Relationship of Topography to Atmospheric Pressure

The relationship between surface topography and atmospheric pressure provides a measure of the mass of the atmospheric column above a particular location, which is critical in the assessment of potential future landing sites [Golombek *et al.*, 1997b, a]. The average atmospheric pressure on Mars is ~ 6.1 mbars, which is close to the triple point of water. Early topographic models of Mars [e.g., Wu, 1991] were referenced to this atmospheric pressure surface. The use of a pressure surface as a reference introduced considerable error into estimates of elevation because of temporal variability in the height of the pressure surface due to seasonal variations in CO_2 content and dynamical motions of the atmosphere. Because of the importance of understanding surface pressure for models of circulation of the Martian atmosphere and for landing-site assessment, MOLA elevations, which are referenced to a static areoid, have been related to the 6.1-mbar atmospheric pressure surface.

To relate surface topography to atmospheric pressure, it is necessary to first compare planetary radii obtained from spacecraft occultations to those derived from MOLA. The occultations yield a measure of both planetary radius and atmospheric pressure and thereby provide a unique linkage between these quantities [Kliore *et al.*, 1973; Lindal *et al.*, 1979; Hinson *et al.*, 1999]. MOLA radii, which are considerably more accurate than radii obtained by occultations, can then be related to occultation-derived surface pressures. By comparing MOLA radii to Viking and Mariner 9 occultations, Smith and Zuber [1998] showed that the zero point of MOLA topography corresponds to an atmospheric pressure of ~ 5.2 mbars at $L_s = 0^\circ$. (L_s is the seasonal parameter on Mars and runs from 0° to 360° over the course of the Martian year; $L_s = 0^\circ$ corresponds to the vernal equinox in the northern hemisphere.) The 6.1-mbar pressure level occurs at approximately -1600 m relative to the zero reference of MOLA topography for $L_s = 0^\circ$. However, the height of the 6.1-mbar surface needs to be adjusted, depending on the

Table 5. Major Topographic Excursions on Mars

Parameter	Latitude (deg)	Longitude (deg east)	Elevation (m)
<i>Regional Highs:</i>			
Olympus Mons ^a	17.3495	226.31	21287.4
Ascraeus Mons	11.7082	255.177	18219.0
Arsia Mons	-9.12736	238.261	17780.7
Elysium Mons	24.7478	146.437	14126.6
Pavonis Mons ^b	-0.0626096	246.674	14057.4
Hecates Tholus	31.8125	149.875	4853.26
Albor Tholus	18.6562	149.875	3925.49
<i>Regional Lows:</i>			
Hellas ^c	-32.8132	62.0172	-8180.
Argyre ^d	-44.8192	315.088	-5240.7
Utopia	39.5	110.2	-5050
Lytot ^e	28.9277	50.6031	-7036.
Valles Marineris	-14.2969	301.969	-5679.47

^arim of small crater on south flank^bsouth rim^csmall crater^dHooke crater^edeepest basin in northern hemisphere

date. Seasonal variations in atmospheric pressure associated with the exchange of CO₂ between the atmosphere and polar caps is expected to produce vertical variations in the height of the 6.1-mbar surface of 1.5 to 2.5 km over the course of a Martian year [Smith and Zuber, 1998].

Comparison to Landing Site Elevations

The Viking and Pathfinder landers contained sensors that measured atmospheric pressure directly and thus provided local estimates of surface elevation. A pre-MGS comparison of Viking lander site elevations with corresponding locations on the USGS DEM shows the heights to disagree by ~ 2 km, with the DEM locations in the wrong relative direction with respect to each other as compared to the lander sites [Kieffer *et al.*, 1992]. In contrast, a comparison of MOLA altimetry with the locations of the landing sites shows good agreement (Table 6), considering the spatial differences in sampling. The differences between MOLA and lander-derived elevations of the landing sites are likely due to actual RMS variations of local topography and (for MOLA) errors in the geoid of Mars that are decreasing as gravity models are continually refined.

Power Spectrum

The power spectrum for Martian topography is obtained from the degree variance of spherical harmonic coefficients [e.g., Bills and Ferrari, 1985]. Figure 5 shows a variance spectrum to degree and order 1152, which corresponds to a spatial scale of 9 km. A power law of

$$\text{Variance} = 8.2815 l^{-1.9346} \text{ km}^{-2} \quad (10)$$

provides a best fit to the spectrum. Figure 5 indicates that Martian topography has less power than the power law from degrees 10-25 (spatial scales $\sim 10^3$ km), due probably to the flat northern hemisphere (discussed later). The increase in power between degrees 100 and 1000 is thought to arise from the cratered southern highlands. At 10-km spatial scale (degree 1000), a 10-m² RMS variance of topography is observed. The power law cannot simply be extrapolated to estimate the RMS variance of surface roughness at landing-site scales. On a 100-m spatial scale only centimeters of roughness would be expected from extrapolation of the power law (Figure 5).

Table 6. Comparison of MOLA to Landing Site Elevations

Landing Site	Latitude ^a (deg)	Longitude ^a (deg east)	MOLA Radius (m)	MOLA Elevation ^b (m)	Elevation MOLA - Lander (m)
Viking Lander 1	22.2692	311.8113	3389373	-3627.	45
Viking Lander 2	47.6680	134.0430	3381857	-4505.	0
Pathfinder	19.0949	326.5092	3389807	-3682.	94

^aLanding site coordinates are taken from *Folkner et al.* [1997]. All locations are given in the IAU1991 reference system [*Davies et al.*, 1992a].

^bMOLA radius minus 50th degree and order areoid of *Lemoine et al.* [2001].




Figure 5. Power spectrum of Martian topography to degree and order 1152. The left axis plots degree variance normalized by the square of the planetary radius, and the right axis plots unnormalized power. The dashed line is a best-fit power law (equation).

Scientific Accomplishments

Global Physiography

COM/COF Offset and the Pole-to-Pole Slope. The 3-km offset along the z -axis between Mars' COM and COF

(cf. Table 4) results in a non-zero $C_{1,0}$ term in the spherical expansion of topography (equation 9). Similarly, the 1.4-km offset in the direction of Tharsis is reflected in the $C_{1,1}$ and $S_{1,1}$ terms in the harmonic expansion. In practice, the term is sinusoidal in latitude rather than linear, so the hemispheric-scale elevation change is more complicated than a constant linear function. If the offset along the polar axis is interpreted in terms of a long-wavelength tilt, then it corresponds to an average global-scale south-to-north tilt of 0.036° directed along lines of longitude [*Smith et al.*, 1999b]. As illustrated in Plate 3, the progressive decrease in elevation from south to north is best observed at longitudes near 0°E , away from the influence of Tharsis and Hellas. While this zonal elevation change is complicated by both large- and regional-scale topographic features, it is apparent that this fundamental aspect of Martian topography has controlled the surface and subsurface flow of volatiles and sediments throughout much of Martian history. As discussed more below, the global-scale elevation change associated with the $C_{1,0}$ term of the topography field resulted in the northern hemisphere becoming a global-scale sink for transported material. As discussed by *Zuber et al.* [1998b], the COM/COF offset in the direction of Tharsis also causes a tilt in the east-west direction, though deflections associated with the membrane response to Tharsis loading complicate the pattern [*Phillips et al.*, 2000].

Hemispheric Dichotomy. The striking difference in global physiography between the northern and southern hemispheres is termed the hemispheric dichotomy [*Mutch et al.*, 1976; *Carr*, 1981]. The southern hemisphere is heavily cratered and older, whereas the northern hemisphere is more lightly cratered and younger, and was probably resurfaced by volcanism [*Scott and Tanaka*, 1986; *Greeley and Guest*, 1987] and sedimentation [*Zuber et al.*, 2000a] early in Martian history. Much of the northern lowlands is composed of




Plate 2. The topography of Mars from MOLA. The resolution of the model is $1/64^\circ \times 1/32^\circ$ ($\sim 1 \times 2 \text{ km}^2$ at the equator). Topography is shown as color-coded elevation draped over shaded relief. Major features are labeled in white. The projection at mid-latitudes is Mercator and at high latitudes is polar stereographic. Coordinates are areocentric with an east positive longitude convention. On Mars 1° is approximately 59 km.

the Late Hesperian-aged Vastitas Borealis Formation and Amazonian-aged Arcadia Formation [Tanaka *et al.*, 1992], which are tilted subtly north and are smooth at scales ranging

from $\sim 100 \text{ m}$ (Plate 5) to baselines of hundreds of kilometers [Kreslavsky and Head, 1999; Aharonson *et al.*, 2001]. In the southern hemisphere, Noachian-aged ridged plains form

locally flat intercrater deposits, whereas younger Hesperian-aged ridged plains dominate in some regions. The boundary between the northern and southern hemispheres in many places is characterized by complex terrain [Sharp *et al.*, 1971; Sharp, 1973], as well as regional elevation changes of up to 4 km over distances of 300 to 1300 km [Frey *et al.*, 1998]. Regions where the elevation change is relatively steep (*e.g.*, longitudes 100° to 220°; see Plate 2), comprise the dichotomy boundary scarp.

The dichotomy is characterized by both an elevation difference (Plate 2) as well as a difference in surface geology and macroscale roughness (Plate 5), but it is not yet clear if these features share the same mechanism of formation. Hypotheses to explain the hemispheric dichotomy have included thinning of the northern hemisphere crust by mantle convection [Lingenfelter and Schubert, 1973; Wise *et al.*, 1979a, b], an early period of tectonic plate recycling [Sleep, 1994], and a massive impact or impacts in the northern hemisphere [Wilhelms and Squyres, 1984; Frey and Schultz, 1988]. The global distribution of elevations from MOLA has some bearing on the nature of the hemispheric elevation difference. Figure 4 shows global hypsograms of elevation with respect to the COM and COF. In a mass-centered coordinate system the elevation difference between the southern highlands and northern lowlands is apparent, while in a figure-centered system the distribution of elevations is unimodal. A planet-scale distribution of topography that contains a discrete elevation contrast in a mass-centered system may, in principle, appear unimodal when referenced to the COF [Aharonson *et al.*, 2001]. However, on Earth, with elevated continents and deep ocean basins, the hypsogram of topography is bimodal whether viewed from mass- or figure-centered systems. This comparison indicates that the dichotomy boundary scarp contributes less to the COM/COF offset on Mars than the continental versus oceanic crust does on Earth [Aharonson *et al.*, 2001].

It has now been established that both the topographic expression [Smith *et al.*, 1999b] and crustal thickness distribution [Zuber *et al.*, 2000a] of the dichotomy boundary are non-circular, and there is no evidence preserved that would support a hemispheric-scale single impact such as previously proposed [Wilhelms and Squyres, 1984]. Formation of the elevation difference by multiple smaller impacts has also been suggested [Frey and Schultz, 1988]. Beyond Utopia, however, no circular structures of comparable scale are apparent in the topography of the northern plains or from gravity [Smith *et al.*, 1999a], although it is possible that such structures could have been masked by processes that occurred subsequent to formation. In any case a process or processes other than impact must be invoked to explain the preserved physiographic difference between the hemispheres.



Plate 3. MOLA pole-to-pole downhill slice along longitude 0° E. The south pole is on the right, and the north pole is on the left. Apparent is the quasi-monotonic decrease in elevation from south to north (apart from the north polar deposits) as well as the distinctive contrast in roughness between the southern highlands and northern plains.

The Northern Lowlands and Evidence for a Possible Ancient Ocean. The northern lowlands display a lower crater density than the southern highlands (*cf.* Plate 2) due to hemispheric-scale resurfacing that, prior to MGS, had generally been viewed as mainly volcanic [Greeley and Spudis, 1981; Greeley and Guest, 1987; Scott and Tanaka, 1986; McEwen *et al.*, 1999], with a thin sedimentary cover in some areas. Analysis of MGS gravity and topography now suggests a significant sedimentary component to the northern hemisphere resurfacing [Zuber *et al.*, 2000a]. The northern latitudes outside of the Tharsis rise are now known to be extremely flat, sloping gently downwards to the north [Smith *et al.*, 1998; Zuber *et al.*, 1998b; Smith *et al.*, 1999b] (*cf.* Plate 3). The flatness of the upper latitudes of the northern hemisphere extends across all longitudes and for over 2000 km in north-south extent. In the northern lowlands the topography varies by only ± 50 m to ± 400 m about a mean sloping surface [Aharonson *et al.*, 1998]. The flatness is observed over a range of topographic baselines [Aharonson *et al.*, 1998, 2001; Kreslavsky and Head, 1999, 2000], and flatness is documented down to the 100-m scale (Plate 5). Of particular interest is Amazonis Planitia (Plate 4), west of the Tharsis rise, that has been established as the flattest large-scale surface in the solar system [Aharonson *et al.*, 1998]. Amazonis exhibits an RMS variance of ~ 2 m over scales up to 10^2 km and is comparable in smoothness to the Earth's oceanic abyssal plains [Aharonson *et al.*, 1998].

Prior to MGS, the northern lowlands were proposed to have been the site of an ancient ocean, with two geological contacts ("1" and "2") hypothesized on the basis of analyses of Viking images as possible shorelines [Parker *et al.*, 1993]. MOLA data were used to test the predictions of the hypothesis of standing bodies of water in the northern lowlands [Head *et al.*, 1998a, 1999; Hiesinger and Head, 2000; Garvin *et al.*, 2000a]. Evidence in support of the hypothesis includes: the correspondence of Contact 2 with an approximate equipotential surface (the ~ 3700 m elevation contour); enhanced topographic smoothness and distinctive simple crater properties inside Contact 2; terraces in the vicinity of Contact 2 that in places are oriented near-parallel to




Plate 4. MOLA Pass 31, which traverses Amazonis Planitia, shows the flat northern hemisphere of Mars. The line connects range returns and the dots show the topography that would be obtained without the instrument's timing interpolator. This figure, in which height is in meters and latitude is in degrees, demonstrates the sub-meter performance of MOLA-2 over gently sloping surfaces.

the contact; and a volume within Contact 2 (~ 100 m global equivalent layer) consistent with estimates of the amount of water that conceivably could have been available on early Mars [Carr, 1996]. An ocean that filled to Contact 2 would have had an average depth of 570 m but would have achieved a depth of over 3 km within Utopia (*cf.* Table 9).

While the evidence from MOLA data is consistent with a past standing body of water, none yet reported uniquely requires such a genesis. Complicating factors include: observations of Contact 2 by the Mars Orbiter Camera that do not show evidence for paleo-shorelines [Malin and Edgett, 1999]; tectonic ridge-like morphology of proposed shoreline terrace features north of Alba Patera and the deviation of these structures from an equipotential surface [Montesi and Zuber, 2000]; statistical analysis of topography that shows that Amazonis and other northern lowland regions cannot be derived from simply smoothing heavily cratered terrain [Aharonson *et al.*, 2001]; and the apparent absence of surficial carbonate in the northern plains noted by the MGS TES instrument [Christensen *et al.*, 2001].

Tharsis. Plate 2 shows the vast volcano-tectonic Tharsis province to consist of a rise that extends from 220°E to 300°E and from 50°S to 10°N , and spans about 10^7 km² by area. The complex structure of the province revealed by MOLA indicates that most of Tharsis was formed by volcanic construction [Solomon and Head, 1981], with likely contributions from both extrusive and intrusive magmatism. The topographic map also shows that Tharsis consists of a main rise that contains the Tharsis Montes (Ascraeus, Pavonis, and Arsia) and a northern rise that essentially comprises the Alba Patera volcanic structure and its

surroundings. The possible contribution to Tharsis topography from structural uplift, whose signature could conceivably have been masked by subsequent volcanism, has yet to be quantitatively assessed.

Unlike all previous topography models, Olympus Mons is not associated with Tharsis proper, but rather is situated off the western edge. However, the volcanic construct likely has a genetic relationship to Tharsis.

MOLA data show that the Thaumasia region that defines southernmost Tharsis is not topographically distinct from the main lobe of the Tharsis rise. High-standing ridges in this region, proposed to be a consequence of lithospheric folding [Schultz and Tanaka, 1994], appear to have escaped resurfacing by younger Tharsis volcanic flows due to their high elevation. These elevated ancient terrains can be a consistent with an origin by either volcanic construction or uplift and further modeling and structural analysis will be required to distinguish the two possibilities.

Previous models for the origin of Tharsis based on gravity and topography analyses supported by the spatial and temporal distribution of tectonics [Banerdt *et al.*, 1982, 1992; Tanaka *et al.*, 1991] are currently undergoing revision [Banerdt and Golombek, 2000]. Contrary to previous conclusions based on lower resolution Viking data [Banerdt *et al.*, 1982, 1992], it is not necessary to invoke a period of purely isostatic support in Tharsis' history. Nor is it necessary to resort to complex representations of Tharsis' mechanical structure, such as an upper crust detached from the upper mantle [Tanaka *et al.*, 1991], though such a lithospheric configuration may have once existed and may explain certain aspects of Tharsis tectonics, such as differences in ridge spacing between Hesperian ridged plains and the northern lowlands [Montesi and Zuber, 2000]. Instead, modeling shows that most structures around Tharsis can be explained by a flexural loading model [Banerdt and Golombek, 2000].

Phillips *et al.* [2001] showed that the membrane response to Tharsis loading has a global-scale effect that can explain a number of salient features on Mars. These include the negative gravity ring around Tharsis [Smith *et al.*, 1999a; Phillips *et al.*, 2000], the elevation of certain terrains in Arabia Terra, and the apparent asymmetry of the Utopia basin rim.

Slopes and Surface Roughness

Slopes. MOLA data have been used to calculate surface slopes on baselines from 300 m to 100 km [Kreslavsky and Head, 1999, 2000; Aharonson *et al.*, 2001]. With the high accuracy of the global data set, slopes on hemispheric-scale baselines (10^3 km) can be measured to several parts in 10^5 . On the 100-km baselines, the predominant tilts are south to north [Aharonson *et al.*, 2001] and are generally consistent

with the mapped distribution of valley networks and outflow channels [Williams, 2000; Phillips *et al.*, 2001].

A useful measure is the RMS slope, which is generally analogous to the RMS roughness from radar observations [Simpson *et al.*, 1992], though this measure is influenced by isolated high slopes associated with structures such as craters within the window. RMS slopes in a 35-km running window show an average of 3° - 10° in the southern highlands and 0.2° - 0.8° in the northern lowlands [Aharanson *et al.*, 2001]. There is a general agreement between RMS slopes from MOLA with those measured by Earth-based radar [Christensen, 1986; Christensen and Moore, 1992], though there are significant disagreements in some regions such as Amazonis Planitia, likely reflecting different RMS slope properties at different length scales [Aharanson *et al.*, 2001].

Median slopes are likely more typical of the average Martian surface, as they are not sensitive to window width and outliers within a window. They are generally smaller than RMS slopes, reflecting the contribution of local-scale structure. For both RMS and median slopes the smoothest units on Mars are Amazonis Planitia and certain parts of the polar caps, while the steepest areas are the walls of Valles Marineris, the Olympus Mons aureole, the dichotomy boundary east of 30° E, and the rims of Argyre and Hellas.

Roughness. At shorter spatial scales, MOLA optical pulse widths show a mean 100-m-scale global roughness of 2.1 ± 2.0 m RMS [Garvin *et al.*, 1999]. The distribution is bimodal with the primary mode at 1.5 m RMS. Less than 1% of all values occur in excess of 10 m, and these are restricted to the flanks of the uplands, canyons, and some larger crater rims. The north and south polar latitudes (*i.e.*, areas north or south of 65° latitude) display a mean roughness of 2.0 m RMS, similar to that for Mars as a whole.

Plate 5, which plots slope-corrected pulse widths, indicates five global roughness units [Garvin *et al.*, 1999], examples of which are given in Table 7. The smoothest units include much of the Vastitis Borealis formation and some parts of the northern polar cap. The roughest areas are clustered in a few distinctive areas, including some parts of the hemispheric dichotomy boundary, the interior of Valles Marineris, and the Olympus Mons aureole.

An interesting aspect of the global roughness distribution is a transition that occurs within the northern lowland plains. Pulse-width-derived roughness correlates with the -3700 m elevation contour (Contact 2) for 60% of the boundary, and follows the crustal dichotomy boundary equally well. More than 50% of the lowermost roughness values on Mars fall within the northern lowland plains, although outcroppings of this unit are also observed in southern mid-latitudes. Another striking regional boundary separates the crustal di-

Table 7. Global Roughness Units from Optical Pulse Widths

RMS Roughness (m)	Example Regions
0.3 to 1.1	Northern plains, Vastitis Borealis, southern hemisphere intercrater plains
1.3 to 1.7	Northern volcanic plains, Amazonis, Elysium, Sinai and Lunae Planum
2.0	Crater ejecta blankets, inner crater cavity walls
2.1 to 2.5	Tharsis, Olympia Planitia
>3.0	Hemispheric dichotomy boundary, Olympus Mons aureole, interior of Valles Marineris

chotomy region from the lowland plains to the north from Arabia to Daedalia Planum.

There is possible evidence for a temporal dependence to surface roughness. The pulse width measurements used in Plate 5 were obtained during southern winter, and the high roughness values on the south polar cap may be at least in part due to the presence of CO₂ frost or snow. But we do not rule out data issues such as might occur when using unsaturated pulse widths but saturated pulse energies. Further analysis is underway.

Impact Craters and Basins

Major Basins. MOLA data have established the Hellas impact structure (Plate 7) as the deepest known topographic depression in the solar system, with relief of over 9 km (Table 5). The basin is topographically asymmetric, which to first order is consistent with the suggestion of an oblique impact [Wichman and Schultz, 1989], but may also reflect localized surface modification (Plate 2). In terms of size, morphology, and topographic expression, Hellas has significant similarities to the South Pole-Aitken basin on the far side of the Moon [Spudis *et al.*, 1994; Zuber *et al.*, 1994; Head *et al.*, 1998d]. These impact structures have similar diameters and volumes, as well as ejecta distributions. Plate 7 illustrates the concentric nature of material around the basin, which has an elevation above its surroundings of 2 km and accounts for a significant amount of the high-standing topography of the southern hemisphere. Material excavated from Hellas represents a major re-distribution of the Martian crust [Zuber *et al.*, 2000a], contributing in part to the surficial ex-




Plate 5. Vertical roughness of Mars in meters at the scale of 100-m from MOLA's optical pulse width. Pulse widths have been corrected for the effect of local slopes as described by *Garvin et al.* [1998]. Map projection and other attributes are as for Plate 2.




Plate 6. Composite 1.064- μm reflectivity of Mars at the scale of 100-m from MOLA's ratio of received to transmitted laser energy measured during the mapping orbit [Ivanov, 2000]. White represents saturated pulse returns, and black corresponds to no data. Each point on the map is an average reflectivity observed over the period $L_s = 100^\circ$ to 360° . Attenuation of the laser power due to extinction from atmospheric aerosols has not been taken into account. The map resolution is $0.5^\circ \times 0.5^\circ$. The map projection and other attributes are as for Plate 2.




Plate 7. Orthographic projection of Martian topography centered on 45°S, 65°E illustrates the annular nature of high terrain (in red) around the Hellas impact basin (at center, in purple). North is to the top; the south polar layered terrains are at bottom center.

pression of topography along part of the dichotomy boundary [Smith *et al.*, 1999b]. Plate 9 shows the unusual distribution of macroscale roughness around Hellas; the southwestern rim is much smoother than the rest of the rim or the surrounding southern hemisphere highlands. This smoothed region has been proposed to be an area of glaciation on the basis of morphology revealed in images [Kargel and Strom, 1992]. Elevation data reveal that basin floor deposits, previously proposed to be a consequence of fluvial, lacustrine, or aeolian deposition [*e.g.*, Wichman and Schultz, 1989], are volumetrically significant.

Precise topography also permits quantitative characterization of both morphometry and unusual aspects of other major impact basins. For example, the MOLA topography now shows a continuous flow route from the Argyre basin to the Chryse outflow region that follows the 0.036° slope, therefore constraining the period in Martian history when transport occurred [Williams, 2000]. Isidis shows a complex floor structure that has no counterpart in images and may reflect distinctive evolution associated with the basin's unique position at the geological dichotomy boundary [Frey *et al.*, 2000b].

Buried and Degraded Basins. MOLA has verified the existence of the Utopia basin, buried beneath the northern




Plate 8. High-resolution regional topographic grid showing detailed evidence for past transport of water in the Chryse region. Locations of the Viking 1 and Pathfinder landers are shown for reference. The unit of elevation is kilometers.




Plate 9. Three-dimensional view of the Hellas impact basin showing the unusually smooth southwest rim. The vertical exaggeration is 20:1. View is from the south.

plains. The basin, centered at 45°N, 110°E (Plate 2), was proposed originally as an impact feature on the basis of geological evidence [McGill, 1989] but was not resolved in earlier topographic maps of Mars. Utopia has a similar diameter to Hellas but its depth is only 2.5 km. Since basin depth scales with diameter, the relief of Utopia indicates that the thickness of resurfacing of the northern hemisphere in the vicinity of Utopia, accounting for uncertainties associated with settling, isostatic adjustment, and Hellas fill, is 5 to 10 km.

MOLA's high-resolution global grid has also resolved a number of subtle, degraded, previously unrecognized impact basins [Frey *et al.*, 1999, 2000a]. There is no MOLA topographic expression [Smith *et al.*, 1999b], however, nor evidence from gravity [Smith *et al.*, 1999a], for some impacts proposed prior to MGS to lie beneath northern hemisphere plains [Frey and Schultz, 1988; Schultz and Frey, 1990].

Impact Crater Geometry. MOLA observations have been used to construct three-dimensional digital elevation models of over 5000 impact craters larger than 7 km in diameter planet [Garvin *et al.*, 2000b]. These measurements include apparent crater depth, as derived from the mean floor elevation and the mean relief of the rim. In addition, we have measured crater cavity and ejecta slopes, cavity and apparent ejecta volumes, cavity shapes, central uplift volumes, and many other parameters. The observations have relevance to understanding the role of target properties, including volatiles, in the impact cratering process [e.g., Carr *et al.*, 1977; Barlow and Bradley, 1990], as well as the influences of crater modification processes [Melosh, 1989].

A particularly useful geometric relationship is the ratio of depth (d) to diameter (D), usually plotted for morphologically distinct crater classes that scale with size. The progressive shoaling of depth relative to diameter as the latter increases reflects the influence of gravity and target strength in the cratering process. For topographically-fresh complex craters in the diameter range 7 to 100 km, the weighted power-law function that best fits the data is [Garvin *et al.*, 2000a]:

$$d = 0.33D^{0.53 \pm 0.03}, \quad (11)$$

where d and D are measured in kilometers. The behavior of complex craters is similar, on a global basis, to results reported by Pike [2000] that were derived on the basis of shadow measurements, but there are significant differences for many individual craters. The result suggests substantial infilling as part of the modification stage, which is consistent with slumping and other effects documented by Mars Orbiter Camera images [Malin and Edgett, 2000].

Equation 11 represents a general shoaling of apparently fresh impact landforms with increasing diameter and hence

kinetic energy. However, there are exceptions, in particular in the higher latitudes on Mars where non-impact-related infilling processes have operated [Garvin *et al.*, 2000b]. The MOLA data have also established a distinctive shoaling of depth at the complex crater/basin transition [Garvin *et al.*, 2000a], similar to that observed for the Moon from Clementine altimetry [Williams and Zuber, 1998].

Because the d/D ratio is sensitive to target properties, it can also be used as an indicator of the shallow subsurface structure. Garvin *et al.* [2000a] analyzed craters within Contact 2 [Parker *et al.*, 1993] and showed that the d/D relationship for simple craters is statistically different from that for the rest of Mars, while that for complex craters shows no notable difference from that for the rest of Mars. This observation suggests that shallow target properties within Contact 2 are different from those outside the contact.

Volcanism

As shown in Figure 6, MOLA data have provided accurate three-dimensional descriptions of a wide range of volcanic edifices (*cf.* Figure 6) and flows [Head, 1998; Smith *et al.*, 1999b]. Measurements such as absolute heights, relief, and volumes (*cf.* Table 5 and Table 8) and the distribution of flank slopes are providing information on volcanic style, composition, and source depth [*cf.* Wilson and Head, 1994]. These data are showing evidence for changes in the characteristics of edifices as a function of geologic time [Head *et al.*, 1998c]. They also are revealing the unusual characteristics of edifices such as Alba Patera, where tectonic structures have been shown to be arrayed asymmetrically around the edifice, and the edifices to extend to much greater distances than previously thought [e.g., Jager *et al.*, 1999; McGovern *et al.*, 2001]. MOLA data also provide important information on caldera depths, volumes and caldera wall structure [Smith *et al.*, 1998], showing the relationships between different morphologic styles and permitting an assessment of their mode of formation and relation to magma reservoirs at depth [e.g., Head *et al.*, 1998b]. Analysis of morphometry has led to the firm identification of an edifice resembling a stratovolcano in the Aeolis region and the development of criteria for the recognition of degraded equivalents in the older heavily cratered terrain on Mars [Stewart and Head, 2001].

Even with high-resolution topography, evidence for flexural loading by volcanic constructs that would provide constraints on lithospheric thickness and heat flow at the time of loading has been largely ambiguous [Solomon *et al.*, 1998]. The lack of any discernible flexural signatures around major structures such as Arsia Mons and Alba Patera implies that any flexural depressions must be filled by some combination of volcanic flows and landslide material from the volcano




Figure 6. MOLA topography draped over Viking MDIM for three volcanic shields: (a) Alba Patera, (b) Arsia Mons, and (c) Olympus Mons. The vertical exaggeration in each frame is 10:1.

flanks.

Detailed measurements of lava flow thicknesses, roughness, levee characteristics and regional slopes are similarly yielding important information on styles of emplacement and rheological properties of lava [Hulme, 1974; Wilson and Head, 1994]. Kreslavsky and Head [1999, 2000] have used MOLA data to characterize the regional and global roughness characteristics of lava flow units and deposits and have found distinct differences between units and trends in roughness characteristics with time. Analysis of individual MOLA profiles has been undertaken as a tool for estimating the rheological properties and silica content of lava flows [e.g., Thomson and Head, 2000]. Analysis of the geometric properties of craters at high latitude has yielded evidence for geologically recent volcanism in the north polar region [Garvin et al., 2000c].

Tectonics

Valles Marineris. MOLA topography has clarified the re-

gional context of the Valles Marineris canyon system, particularly its relationship to the Tharsis province. Valles Marineris is now shown to lack a regional dome, which indicates that the canyon system was a consequence of passive rifting [Sengor and Burke, 1978] associated with stresses due to the formation of the Tharsis rise [Smith et al., 1999b], rather than an active rift formed above a localized mantle plume. The canyon system dips to the east away from Noctis Labyrinthus, reaching a maximum depth of approximately 11 km below the surrounding Hesperian-aged plains. The easternmost segments of Valles Marineris tilt westward and are situated a kilometer below Chryse, where outflow channels suggest water from Valles Marineris and other southern hemisphere regions once debouched. The westward tilt initiates at the intersection of the canyon with an outcropping of Noachian material surrounding Solis Planum and predates the formation of the canyon, suggesting that the westward tilt has existed since the canyon formed. The topographic configuration of the eastern canyon could be consistent with the transport of significant quantities of water in earlier periods [Smith et al., 1999b]. The canyon walls exhibit a duality of slopes from top to bottom such that the upper wall sections are steeper than their lower counterparts [Aharonson et al., 1998]. Such a slope distribution indicates extensive mass wasting related to the slumping and erosion of material from the upper walls.

Graben. MOLA profiles have been used to estimate Tharsis-related tectonic extension in the Tempe Terra region in eastern Tharsis. The results for extension in small graben are generally consistent with earlier work [e.g., Golombek et al., 1996] based on scarp widths and assumed scarp slopes. However, MOLA-derived extension in large rifts is less, because measured slopes are now known to be less [Harrington et al., 1999] than estimated in previous work.

Wrinkle Ridges. MOLA profiles and gridded data have elucidated the nature of wrinkle ridges, are compressive structures characterized by linear, asymmetric topographic highs that are preferentially found in volcanic plains. A long-standing question has been the subsurface structure of the ridges, their depth penetration, and the contributions of faulting versus folding in accommodating strain [e.g., Plescia and Golombek, 1986; Watters, 1993; Zuber, 1995]. MOLA topography shows that the preponderance of ridges exhibit an elevation offset [Golombek et al., 2001], a result that appears most consistent with the presence of a subsurface fault with significant depth penetration, a style of faulting also termed "thick-skinned" deformation. The topography also shows that, at least in the Tharsis region, the elevated side of grouped ridges is consistently on the same side, which may be a consequence of heterogeneities in the stress field or lithospheric structure of Tharsis at the time of ridge

Table 8. Relief and Volumes of Major Volcanoes

Volcano	Latitude (deg)	Longitude (deg E)	Maximum Elevation (m)	Basal Elevation (m)	Relief (m)	Edifice Volume ^a ($\times 10^6$ km ³)
Alba Patera	40.5056	248.110.	6769.6	827.	5942.6	2.1
Arsia Mons	-9.12736	238.261	17780.7	5823.	11957.7	1.5
Ascraeus Mons	11.7082	255.177	18219.0	3401.	14818.0	1.1
Elysium Mons	24.7478	146.437	14126.6	1793.	12333.6	0.2
Olympus Mons	17.3495	226.31	21287.4	-378.	21665.4	2.7
Pavonis Mons	-0.0626096	246.674	14057.4	5807.	8250.4	0.4

^aVolumes were calculated by estimating the position of the base of the volcano (usually a break in topographic slope, and including the prominent flank eruption deposits on the Tharsis Montes) circumferentially around the edifice, determining the average elevation of this surface, and calculating the volume above this average elevation. No correction was made for the influence of lithospheric flexure or of infilling of flexural moats by flows or slide material [McGovern and Solomon, 1993, 1997].

formation [Montesi and Zuber, 2000].

Internal Structure

Crustal Structure. MOLA topography, in combination with gravity [Smith *et al.*, 1999a; Lemoine *et al.*, 2001] from the MGS Radio Science experiment [Tyler *et al.*, 1992, 2001], has permitted determination of the global crust and upper mantle structure of Mars [Zuber *et al.*, 2000a]. In an inversion for crustal structure based on a uniform-density crust [Zuber *et al.*, 2000a], the planet displays two distinct crustal zones that do not, at least in the present day, correlate globally with the geologic expression of the hemispheric dichotomy. One crustal province consists of a region of crust that thins progressively from the south polar region toward the north, and encompasses much of the southern highlands and Tharsis province. The second province constitutes a region of approximately uniform crustal thickness that includes the northern lowlands and Arabia Terra. While the boundary between crustal provinces lacks correspondence to the geological dichotomy boundary, it does show some correlation to distinctive global-scale compositional units mapped by the MGS TES instrument [Bandfield *et al.*, 2000]. On a regional scale, the model shows thinning of the crust beneath major impact basins and a complex crustal structure beneath Tharsis indicative of pervasive accumulation of volcanic materials. As for terrestrial rift zones, the crust beneath Valles Marineris is thinned along the central axis. The Elysium and Solis Planum provinces appear to be crustal plateaus with crustal roots, while Tempe Terra is a topographic dome that lacks a root.

The mean thickness of the global crustal model (~ 50 km) is constrained by calculations of the minimum value of lower-crustal viscosity that allows the long-wavelength crustal structure to be maintained [Zuber *et al.*, 2000a]. The results are inconsistent with alternative models that suggest an average crustal thicknesses of 100-250 km on the basis of the geochemistry of Martian meteorites [Sohl and Spohn, 1997] or inappropriate isostatic assumptions [Yuan *et al.*, 2001].

Lithosphere Structure. MGS topography and gravity have also been used to map the thickness of the elastic lithosphere on Mars, which is a measure of the inverse of the thermal gradient, and thus of heat flow from the interior [Solomon and Head, 1990]. Prior to MGS, Martian lithosphere thickness was estimated from the flexural deflection of the lithosphere in response to loading, but analyses were limited by the resolution and quality of the topography, and to a lesser extent, gravity fields. Earliest estimates of the thickness of the elastic lithosphere on Mars were derived from the radial distances of circumferential graben inferred to be the result of flexural stresses from near-axisymmetric loads [Comer *et al.*, 1985], or from the absence of graben around a known load [Comer *et al.*, 1981].

Independent inversions and forward models [Simons *et al.*, 1997, 2000; McGovern *et al.*, 2001] have been performed for effective elastic thickness T_e , regarded as the depth to an isotherm ($\sim 650^\circ\text{C}$) beneath which the Martian interior is too weak to support stresses over geologically-long ($\sim 10^8$ year) intervals. Results indicate considerable spatial variability in lithosphere structure. For example, the southern highlands, including the Hellas impact basin, show a best-fit

T_e ranging from 0 to 20 km, while the Utopia basin in the northern plains gives a value of ~ 100 km. The Alba Patera volcano displays $T_e = 50$ km, while Olympus Mons and the other Tharsis volcanoes are characterized by $T_e > 100$ km. Within the southern highlands, the Terra Cimmeria region of prominent linear magnetic anomalies revealed by the MGS magnetometer experiment [Acuna *et al.*, 1999; Connerney *et al.*, 1999] shows $T_e = 20$ km.

The lithospheric thickness distribution is explained if, as on Earth [Watts *et al.*, 1980], elastic thickness reflects the thermal state of the Martian lithosphere at the time of loading [Zuber *et al.*, 2000a]. The southern highlands have the oldest surface ages, and the T_e values are consistent with crustal stabilization and loading earliest in Martian history. Next youngest are the northern lowlands, and the lithosphere thicknesses derived reflect the thermal state during the period of northern hemisphere resurfacing. The lithospheric thicknesses determined for large areas of the southern lithosphere indicate a heat flow on early Mars, however, that is considerably less than the global averages suggested by many thermal evolution models [Schubert and Spohn, 1990, 1998]. If this difference is valid, then much of the early heat loss must have been localized elsewhere on Mars, in a region or regions where lithosphere thicknesses at the earliest times cannot be determined because values in such regions reflect the thermal state at times of subsequent geological activity. On areal grounds, the northern hemisphere was the most likely locus of any such early high heat flow. Such an inference could be consistent with an early episode of plate tectonics [Sleep, 1994], a period of degree-one mantle dynamics [Zhong and Zuber, 2000], or perhaps some other global-scale geodynamical phenomenon.

Past Transport of Water

Channels. Martian outflow channels represent compelling evidence for the transport of significant quantities of water during earlier evolutionary epochs on the planet [Carr, 1996]. However, significant questions remain regarding the amount, duration, and possible episodicity of flow and the residence time of liquid water on the early Martian surface [Carr and Clow, 1981; Baker *et al.*, 1991]. MOLA altimetry has permitted precise characterization of local and regional slopes as well as channel cross sections that are enabling past estimates of flow rate and discharge [cf. Komar, 1979; Komatsu and Baker, 1997] to be refined [Smith *et al.*, 1998].

Thus far, high-resolution profiles and regional topographic maps, such as shown in Figure 8 for the Chryse outflow region, have yielded evidence for sustained flow and multiple flooding events [Williams *et al.*, 2000]. In addition a global analysis of the geometric properties of valley networks has revealed a correlation of channel depth with lat-

itude [Williams, 2000] that may have implications for the volatile source depth. These observations, combined with the recognition of linear gravity deficits that emanate from major outflow regions and may represent the subsurface continuation of channels in Chryse and Kasei Valles [Zuber *et al.*, 2000a]. These proposed buried channels collectively have implications for the early transport of water, in terms of the mechanism for liberating liquid water, the duration of flow, and the nature of filling of a proposed early ocean.

Watersheds. While it is not possible to confidently reconstruct past pathways of water on Mars from present topography, MOLA data can be used to trace current transport directions and sinks. There is reason to believe that Mars has not undergone major vertical motions for much of its history [Banerdt and Golombek, 2000; Williams *et al.*, 2000; Williams, 2000], so such analysis may also have significant relevance for the nature of surface and subsurface hydrological transport that occurred in an early environment when liquid water was stable at the surface.

Flow directions and watersheds based on the present topography have been calculated globally for Mars [Smith *et al.*, 1999b]. Figure 10 indicates that there are at present, and probably for much of Martian history, four major closed basins that can act as sinks for the surficial flow of water or ice. The low-lying northern plains is by far the largest of these basins. Table 9 shows that its watershed, the basin along with the remaining area of the planet that would drain into it, constitutes three-quarters of Mars' surface area. Table 9 also shows watershed characteristics for Contacts 1 (-1700 m) and 2 (-3750 m), defined by Parker *et al.* [1993] as possible locations of ancient shorelines. Note that the volume estimate for Contact 1 can only be considered approximate because it deviates significantly from a constant elevation [Head *et al.*, 1999].

The other basins are Hellas, Argyre, and Solis Planum, all in the southern hemisphere. Hellas is much smaller in area than the northern plains, but its great depth gives it a volume that approaches that of the much shallower northern basin, though volume ultimately depends on the amount of water available for fill. The highest closed contour of the Hellas drainage basin is 1250 m, at which level it breaches into the Isidis basin and into the northern lowlands. However, Hellas' drainage area is relatively small. The volume of Argyre is only 8% that of Hellas, but its drainage area is about half as large. Argyre's watershed breaches into Chryse Planitia through a well-developed set of flood-carved channels that may have removed a significant volume of surficial material from the highlands [Hynek and Phillips, 2001]. The high elevation (3300 m) and shallow depth (~ 500 m) of the Solis Planum watershed dictate that given sufficient fill it may have breached and combined with Argyre [Williams, 2000].

Table 9. Mars Watershed Characteristics

Basin	Drainage Area (10^6 km^2)	Basin Volume (10^6 km^3)	Flooded Area (10^6 km^2)	Overflow Elevation (m)	Maximum Depth (m)	Average Depth (m)
N. Plains (above -3750 m)	110.85	14.05	24.82	N/A	3215	570
N. Plains (above -1700 m)	110.85	93.21	51.00	N/A	5165	1830
Hellas	22.34	27.24	10.61	1245	9465	2570
Argyre	11.41	2.27	1.48	185	5140	1530
Solis Planum	2.89	0.36	0.79	3310	1800	460




Plate 10. Drainage basins and watersheds on Mars for the three largest closed basins based on present-day topography. The northern plains basin is dark blue, and its watershed is pink. The Hellas basin is purple, and its watershed is orange. The Argyre basin is turquoise, and its watershed is green. For limited amounts of fill the high-standing Solis Planum region would be a separate basin.

Polar Regions

North Polar Cap. The north polar cap (Plate 2) stands ~ 3 km above the surrounding terrain but lies within a ~ 5 -km-deep hemispheric-scale depression that is contiguous with the northern lowland regions [Zuber *et al.*, 1998c]. The regional setting of the northern cap clarifies the nature of solar insolation [Ward, 1974; Arrell, 2000] and provides a quantitative basis for model of the global cycling of water [Clifford, 1993] throughout Martian history. Observations from Viking showed a water-ice composition for the residual north polar cap [Paige *et al.*, 1994]. Both ablation and viscoplastic flow have been shown to be consistent with broad-scale aspects of the overall shape [Zuber *et al.*, 1998a; Ivanov and Muhleman, 2000; Zwally and Saba, 1999].

The northern cap displays complex structure, including deep spiral chasms that penetrate in some cases to the level

of surrounding terrains (*cf.* Figure 7). MOLA reflectivity measurements (Plate 6) verify that these chasms are a sink for windblown dust. Small-scale layering visible at the margins of the cap from high-resolution imaging [Thomas *et al.*, 2000] is not resolved in MOLA altimetry. Large areas of the ice cap are extremely smooth, with regional slopes over many tens of kilometers of order 0.2° . Topography on spatial scales of kilometers has been observed in some areas to be smooth at the meter scale at 100-m spatial resolution (Plate 5). Deposits outward of the main cap show regional slopes that are comparable to those observed in association with the central cap deposits, but the outer terrains exhibit more small-amplitude variation than the central cap deposits. Such topographic variance may be indicative of stagnant ice in the outlying deposits. Gravity anomalies do not correlate well with the northern polar deposits [Smith *et al.*, 1999a], suggesting either a nearly compensated load or complex subsurface structure [Johnson *et al.*, 2000].

Impact craters in high-latitude terrains that surround the north polar cap display unusual geometric and reflective properties that collectively constitute evidence for ice fill [Garvin *et al.*, 2000b], attesting to the significant volatile content of the substrate at high latitudes.

Spiral chasms are observed to penetrate into the massive Olympia Planitia dune field, which supports the suggestion that this region was one a part of the polar cap and subsequently lost volatiles. Topography and statistical analysis of correlation length [Aharonson *et al.*, 2001] indicates that the Olympia Planitia dune field is unique on Mars in terms of its regularity in wavelength structure. The volume of the dune deposit is $10,000 \pm 3000 \text{ km}^3$, with the accuracy limited by the uncertainty of the position of the basal surface.

South Polar Cap. The southern ice cap (Plate 2) lies at an elevation ~ 6 -km higher than the northern cap due to the 3-km offset between Mars' COF and COM [Smith and Zuber, 1996; Smith *et al.*, 1999b]. The southern cap is visually




Figure 7. Profiles from the MOLA global grid across the (*left*) northern and (*right*) southern polar caps at 20° longitude intervals. Apparent are the general planform of the layered terrains as well as the spiral chasms, surrounding terrain, outliers, and impact craters. The vertical exaggeration is 100:1.

much smaller than in the north, although south polar layered deposits extend much farther from the ice cap and exhibit a more asymmetric distribution than their northern counterparts [Zuber *et al.*, 1998c]. The residual ice, which persists throughout the seasonal cycle, is offset from the present rotational pole toward $35^\circ - 40^\circ\text{E}$ such that the pole does not fall within the residual ice deposits. The topography is highest in the south polar region within the residual ice deposits (87°S , $\sim 10^\circ\text{E}$), where a broad dome is present at one end of the cap (*cf.* Figure 7). The relief of the southern polar cap is comparable to that of the northern cap (Table 10).

The topography indicates that the area of probable ice-rich material greatly exceeds the region of residual ice that is apparent from images. This conclusion is based first on the existence of distinctive plateau regions that correlate with layered terrain units, as would be expected if the layers were deposited on cratered terrain [Vasavada and Herkenhoff, 1999]. Unlike the situation in the north, a well-defined gravity anomaly correlates with the southern layered deposits, indicating that the southern layered terrains are uncompensated [Smith *et al.*, 1999b].

Impact craters within the layered terrains share unusual

Table 10. Polar Layered Terrains

Parameter	North	South
Maximum elevation (m)	-1905.2 ^a	4802.5 ^b
Maximum relief (m)	2744.8 ^c	3052.5 ^d
Mean elevation (m)	1015	783.3
Area ($\times 10^6$ km ²)	1.12	1.16
Volume, no flexure ($\times 10^6$ km ³)	1.14 ^c	1.20 ^d
Volume, with flexure ^e $\rho_{cap} = 1000$ kg m ⁻³ ($\times 10^6$ km ³)	1.505 ^f	1.66 ^g
Volume, with flexure ^e $\rho_{cap} = 2000$ kg m ⁻³ ($\times 10^6$ km ³)	2.34 ^f	2.70 ^g

^a (89.7353°N, 220.366°E)^b (87.1362°S, 348.116°E)^c above -4650 m^d above 1750 m^e The total volume is assumed to be the topography above the basal surface plus the material filling the flexural depression calculated as in *McGovern and Solomon* [1997].^f assumes $T_e = 50$ km after *Zuber et al.* [2000a]^g assumes $T_e = 30$ km after *Zuber et al.* [2000a]

geometric properties with counterparts in the north polar region [*Garvin et al.*, 2000b] that are observed to have formed in an ice-rich substrate. This similarity suggests that significant portions of the south polar ice cap may be buried beneath mantling dust deposits.

The detection by Viking of CO₂ within south polar residual deposits during summer seasons [*Paige and Keegan*, 1994] suggested a dominant CO₂ composition. However, topographic cross-sections across the northern and southern caps (Figure 7) show a correspondence in shape that, combined with recent results on the rheology of solid CO₂ [*Durham et al.*, 1999], suggests that the southern cap may have a significant water ice component [*Nye et al.*, 2000].

Present Volumes and Past History. The polar caps represent one of the two major reservoirs of present-day volatiles on Mars, with the other being the subsurface regolith [*Carr*, 1996]. The layered terrains are the only reservoir whose volume can be realistically estimated on the basis of current observations. Best estimates for volumes, taking into account the possible effect of lithospheric flexure due to loading of the polar deposits [*Smith et al.*, 1999b; *Johnson et al.*, 2000], are given in Table 10. To determine upper limits of

the volume, the models use elastic plate thicknesses, T_e , determined by *Zuber et al.* [2000a], which reflect the mechanical structure of the lithosphere at an earlier epoch. At such time the elastic lithosphere would have been thinner than at present and greater flexural deflection would have occurred in response to loading. Lower limits of volume were determined from the limit of an infinitely thick lithosphere, with no flexural deflection and where the volume consists of material above the basal surface. For all flexural models $\Delta\rho = \rho_{mantle} - \rho_{cap}$, where ρ_{cap} ranges from 1000 kg m⁻³ to 2000 kg m⁻³, with the former value corresponding to pure water ice and the latter to an ice/dust mixture. Uncertainties in the volume include uncertainties in the densities of the polar layered deposits and in the lithosphere thickness, as well as the extent of ice-rich material, particularly in the south. Densities of the polar deposits can be calculated from the gravitational load, but such estimates are model dependent because they require knowledge of the position of the basal surface and the compensation state of the load. In addition, estimates of the polar deposit load from gravity alone do not take into account the possible effect of lithospheric loads beneath the caps, which appear to be present at least in the north polar region [*Smith et al.*, 1999b; *Johnson et al.*, 2000]. The combined northern and southern layered terrain volumes can be expressed in terms of a global equivalent layer (GEL) of water. This estimate of the present-day surface water inventory is obtained from the "no-flexure" lower limit and from the flexural estimates assuming purely water-ice ($\rho_{cap} = 1000$ kg m⁻³) caps. The results yields a GEL of 16 to 22 m, which is at the low end of estimates for the amount of water believed to have been present early in Martian history [*Carr*, 1996].

There is evidence that both polar caps were once larger than at present. "Outliers" of high-albedo material detached from the northern cap are now shown to exhibit up to a kilometer of relief and represent massive volatile-rich deposits [*Zuber et al.*, 1998c]. These structures are distributed quasi-symmetrically around the present cap and may delineate the bounds of a larger cap earlier in Martian history [*Fishbaugh and Head*, 2000].

Regional-scale topography in the distal region of the southern layered deposit reveals evidence for a volatile-rich layer of Hesperian age. The morphology suggests the possibility of sub-glacial meltback and possible drainage of liquid water into surrounding lows, including the Argyre basin, in middle Martian history [*Head*, 2000].

The age of formation of the polar caps is not well constrained given the small number of preserved impact craters, though crater counts [*Cutts et al.*, 1976; *Plaut et al.*, 1988] and morphology [*Thomas et al.*, 2000] suggest that the upper surfaces of the south are older than that of the north. Anal-

ysis of MOLA topography over the north polar cap has resulted in an increase in the number of craters and an increase in the upper limit of its relative surface age [Sakimoto and Garvin, 1999], but such analysis is limited in interpretability as it does not yet take into account the obliteration and relaxation of these structures. It is not yet understood whether the difference in apparent compensation states between the southern and northern layered terrains [Smith *et al.*, 1999a] is due to differences in lithosphere structure, age of loading, or the composition of the load (*e.g.*, a higher dust content in the southern cap).

Mars '98 Landing Site

In anticipation of the Mars Polar landing in December 1999, the MOLA team provided to the Mars '98 Project information on surface topography, landing site pressure, and local slopes of the landing region (70°S to 80°S; 130°E to 210°E) to be used in landing site assessment. Subsequent to a planned loss of signal prior to the atmospheric entry phase of the terminal descent to the surface, communication with the lander was never re-established. During attempts to locate the lander, updated MOLA information was provided to the Mars '98 Project, and additional information on local slopes and surface roughness was later provided to the Mars Polar Lander Failure Board [Casani *et al.*, 2000] for their evaluation of environmental factors that may have contributed to the failure.

Plate 11 shows the topography in the vicinity of the most likely landing area (76.5°S; 165°E) based on a post-landing reconstruction developed from the best-available navigation information and atmosphere models. The elevation of the likely landing site is 2424 m, and at the time of the landing ($L_s = 256^\circ$) the atmospheric pressure is estimated to have been ~ 5 mbar, well within acceptable limits [Casani *et al.*, 2000]. Plate 11 shows that most of the area is smooth relative to most of Mars. Within the landing region, however, there is a large depression. This structure is characterized by 300-m baseline slopes that are mostly less than 5°, within acceptable landing limits. But approximately 1% of the area has slopes greater than 10°, in excess of the design specifications for landing.

The contours in Plate 11 show the 100-m-scale RMS roughness derived from MOLA's returned optical pulse widths. These roughness values have been corrected for the effects of local slopes [Garvin *et al.*, 1999]. Over most of the landing zone, the pulse width correlates well with the larger-scale slopes, behavior contrary to the norm for most of Mars (*cf.* Plate 5). This result indicates that the pulse spread is most likely due to the regional slope and that the surface at 100-m-scale is smoother than for most of Mars. This interpretation is consistent with recently re-analyzed thermal inertia




Plate 11. Topography (shaded contours) and 100-m-scale roughness (line contours) of the Mars Polar landing region. The most likely landing point is (76.5°S, 165°E) [Casani *et al.*, 2000].

results [Vasavada and Herkenhoff, 1999] that suggest that the landing area is dominated by a dust-covered surface with minimal to no rock cover (see also [Casani *et al.*, 2000]).

1.064- μ m Reflectivity

Plate 6 shows the composite reflectivity of the Martian surface and atmosphere at 1.064 μ m from MOLA. The map shown is a time-averaged value at each grid point. When the TES investigation produces corrected opacity data, it will be possible to produce a global map of 1.064 μ m reflectivity for the surface alone. In practice, the reflectivity of the surface changes with the seasons due to the advance and retreat of the polar frosts and because of dust re-distribution.

In the current composite map the Tharsis region is the brightest on the planet and lacks significant atmospheric aerosols, so most of the laser returns in that region are saturated. The north polar ice cap is unsaturated primarily because of extinction in extensive cloud formations that existed over the cap during northern fall and winter. However, the north polar signature became largely saturated during periods when the atmosphere was clear. The darkest places on the planet are Acidalia Planitia, Utopia Planitia, and the floor




Figure 8. CO₂ snow condensing out of the Martian atmosphere over the south pole during southern hemisphere winter during the first day MOLA turned on in the mapping orbit. The filled circles correspond to channel 1 and 2 returns and the small and large open circles correspond to channel 3 and 4 returns.

of Valles Marineris. Acidalia and Utopia are well-known dark albedo features. Returns from the dark floor of Valles Marineris are also attenuated by the dust within the canyons [Ivanov and Muhleman, 1998]. Overall, there is a good correlation of the reflectivity with dark and bright albedo features on the surface of Mars.

Clouds and Snow

Volatile clouds detected by MOLA are generally of two types: bright or reflective structures that are sufficiently backscattering that they result in detections, and dark or absorptive features so opaque that no returned signal is obtained [G. A. Neumann and Zuber, 2001]. Clouds detected by MOLA are typically denser than telescopically-observed hazes, although they often coincide [Ivanov and Muhleman, 1998]. Zonal plots of the temporal distributions of reflective and non-reflective or absorptive clouds are shown in Plate 12.

Observations of reflective clouds by MOLA began just after orbit insertion with limited coverage of the north polar hood during late northern winter, $L_s = 305^\circ$. As shown in Plate 12a, reflective clouds in the north polar region begin to develop in northern autumn ($L_s \sim 200^\circ$), peaking in density and southward extent by $L_s = 280^\circ$. They then recede poleward, dissipating prior to the beginning of spring. At the




Plate 12. Zonal plots of number of frames in which (top) reflective and (bottom) non-reflective clouds have been observed within a 2° window of latitude and a 2° window of season (L_s) during the MGS mapping orbit. Reflective clouds detected during the SPO mission phase are shown as an outset above the mapping figure. Because of the sensitivity of returned signal strength to spacecraft orbit geometry, non-reflective clouds are not easily identifiable during SPO. From G. A. Neumann and Zuber [2001].

commencement of global mapping during southern winter ($L_s = 104^\circ$), reflective clouds appeared high over the southern pole (e.g., Figure 8), with low, dense clouds flanking the pole at 70°S . As for the north, these clouds disappeared by the beginning of spring.

Plate 12 suggests that the north polar reflective clouds may have persisted longer in the 1998 winter season than




Plate 13. Spatial distributions of number of frames in which (a) reflective (white dots) and (b) non-reflective (black dots) clouds were observed by MOLA. Both plots represent temporal averages of mapping orbit observations. From G. A. Neumann and Zuber [2001].

they did in 2000. Observations were limited to twice a day during elliptical orbit mapping, yet overall more clouds were seen around $L_s = 350^\circ$ in 1998 than during the mapping orbit in 2000, when observations were about six times more frequent. However, the data have not been scrutinized for possible temporal effects of pulse energy and other factors, so the data warrant further review.

Plate 12b shows a much different distribution of absorptive clouds. In the northern polar regions absorptive clouds developed during northern autumn and trace the north polar frost line. Their occurrence decreases during northern winter, during which time the reflective clouds dominate. The number of cloud frames increases again during late winter. In the southern hemisphere, a separate dark cloud front formed north of the polar frost line. As southern winter ended, the cloud line migrated southward toward the pole, clearing by southern summer solstice. As for the north, dark

clouds are not observed in areas where reflective clouds are seen over the southern polar deposits.

During southern hemisphere summer at about $L_s = 220^\circ$ through 250° , non-reflective clouds became globally distributed. During this period there were major dust storms that were also observed by the TES [Smith et al., 2000; Conrath et al., 2000] and MOC [Malin et al., 1998] instruments.

Plate 13 shows that the spatial distribution of clouds is geographically and topographically controlled [G. A. Neumann and Zuber, 2001]. There are many more non-reflective clouds than reflective ones, with the former located mostly in topographic lows, along the seasonal frost lines, and in association with dust storms, and the latter found mostly in the polar regions. Both bright and dark northern winter clouds are concentrated in the Borealis basin, and the dark clouds penetrate southward into Chryse. Cloud fronts, with unusually sharp returns (mainly channel 1), are distributed broadly over the southern cap in winter. Many craters show clouds closely associated with their rims. Atmospheric reflections have also been observed to obscure periodically some high-latitude craters that have bright floors indicating the presence of frost or ice [cf. Garvin et al., 2000b]. Absorptive clouds are seen in the Hellas Basin (50° to 80° E) almost year-round. Equatorial clouds have also been observed within the Valles Marineris and Noctis Labyrinthus canyons.

Cloud echoes have been observed at elevations as high as 15 km above the surface [Pettengill and Ford, 2000; G. A. Neumann and Zuber, 2001]. Due to the typical width of the MOLA range gate (20 km), the maximum elevations observed by the instrument likely do not correspond to actual maximum heights. Clouds are sometimes observed to have sloping tops that are interpreted as propagating phase fronts of gravity or buoyancy waves [Zuber et al., 1998c; Pettengill and Ford, 2000]. These waves are likely generated by the heat of fusion associated with the condensation of CO_2 or by polar geostrophic winds. Also observed are lee waves generated by the impingement of polar vortex winds [Zurek et al., 1992] on topographic discontinuities such as the margins of polar layered terrains.

Early theoretical considerations and general circulation model calculations [Geirasch and Goody, 1968; Leovy and Mintz, 1969] first addressed possibility of CO_2 condensation in the Martian atmosphere. Subsequent IR spectral measurements of the atmosphere [Forget et al., 1995; Bell et al., 1996; Klassen et al., 1999] and polar caps [Paige et al., 1994; Paige and Keegan, 1994] supported this possibility. The reflective clouds detected by MOLA condense during the winter night and sublimate in sunlight. The observation of visible-IR phase fronts dictates that the condensing volatile is almost certainly solid CO_2 . Thus these reflective




Plate 14. Part of MOLA profile P10769b showing returns south of the Valles Marineris during a regional dust storm in Noachis Terra.

clouds represent the first height detections of dry ice snow in the Martian atmosphere. The observations indicate that the atmospheric lapse rate follows a "wet" CO_2 adiabat of $0.85^\circ \text{ km}^{-1}$ [Zuber *et al.*, 1998c; Pettengill and Ford, 2000].

As shown in Plate 14, MOLA has also observed regional dust clouds. These optically thick clouds form at low altitudes (within 1 km of ground) in localized areas at equatorial and low southern latitudes. Dust clouds, which have been independently imaged/detected by the MGS MOC [Malin *et al.*, 1998] and TES [Christensen *et al.*, 2001] instruments, have been observed by MOLA to obscure the floors of Valles Marineris and the Hellas basin. Given the forward-scattering properties of dust, clouds such as shown in Plate 14 observed during a dust storm in Noachis Terra and during dusty atmospheric periods in Figure 12b may correspond to water ice clouds condensed on dust grains.

Increases in atmospheric opacity have also been observed from MOLA's reflectivity measurement during the SPO mission phase [Ivanov and Muhleman, 1998]. Higher than average atmospheric opacity was observed within the Valles Marineris and at high northern latitudes. Given the preliminary nature of the analysis it was not possible to distinguish whether the increase was due to dust or CO_2 , though this should be possible in the future by joint analysis of MOLA observations with TES [Christensen *et al.*, 2001] and IRTM [Kieffer *et al.*, 1977] data.

Phobos

On September 12, 1998, MGS encountered the Martian moon Phobos at a distance of 265 km, which was well within the MOLA ranging distance. A scheme was developed to maximize the ranging time to the moon by overtaking the trailing rim with the spacecraft slew while at a distance (~ 530 km) such that the apparent motion of Phobos was less than 0.3° s^{-1} . As the track crossed Phobos and the distance decreased, the increase in apparent motion slowed and eventually reversed the track before the entire disk was traversed. The track then re-crossed the trailing rim at a range of ~ 350 km (Plate 15). This operation resulted in the first success-




Plate 15. (a) Location of MOLA profile of Phobos plotted on the shape model of Duxbury [1989]. (b) Profile plotted as radius from Phobos' center of mass.

ful active ranging to a small body, with nearly 70 seconds of time on the target and 627 valid ranging measurements along two nearly co-incident but slightly offset tracks [Banerdt and Neumann, 1999]. These tracks cross Phobos' Mars-facing hemisphere and span a distance of $\sim 120^\circ$ of arc. At these distances the laser footprint varied in size from 130 to 200 m near the reversal point to a few hundred meters near the limb. Successful returns were obtained for emission angles up to 80° . Plate 15 shows that the MOLA profile sampled a variety of craters and provided information on laser performance when ranging near the limb of a body of finite size. The MOLA ranging observations also indicated a 4-km offset of Phobos relative to the expected position [Banerdt and Neumann, 1999] and have been used to improve the ephemeris of the body.

Conclusions

MOLA has successfully mapped the global topography of Mars with a horizontal resolution a couple of kilometers and a vertical accuracy of ~ 1 m. In addition, the instrument has provided global information on surface roughness, $1.064\text{-}\mu\text{m}$ reflectivity, and the spatial and temporal distribution of clouds and snow. In the rest of the MGS mapping mission, the goals of the MOLA investigation are to fill in and further refine the global map in terms of spatial resolution and vertical accuracy. In addition, there will be increased effort to produce high-resolution regional topographic grids (*e.g.*, Plate 8), and to improve measurements of optical pulse width and reflectivity. During the extended mission, MOLA's primary goals will be to attempt to resolve

time variations in the elevation due to the seasonal exchange of CO₂ between the atmosphere and polar caps, as well as to monitor changes in the atmosphere due to CO₂ and dust transport. Finally, the generation of high-resolution local grids of topography, slope, and surface roughness to assist in the identification and assessment of potential future landing sites will be a high priority.

Acknowledgments. The MOLA investigation is supported by the NASA Mars Exploration Program. We recognize significant contributions from R. B. Follas, J. J. Frawley, S. K. Fricke, P. L. Jester, S. Pratt, J. Quigley, J. H. Roark, J. C. Schott, B. Webb, and M. Wong. In addition we acknowledge the MOLA instrument engineers, the laser engineers at McDonnell-Douglas, and the Mars Global Surveyor spacecraft and mission operation teams at the Jet Propulsion Laboratory and Lockheed-Martin Astronautics for their contributions to the success of MOLA. Data and further information about the MOLA investigation can be found at <http://ltpwww.gsfc.nasa.gov/tharsis/mola.html>.

References

- Abshire, J. B., X. Sun, and R. S. Afzal, Mars Orbiter Laser Altimeter: Receiver model and performance analysis, *Appl. Optics*, 39, 2440–2460, 2000.
- Acuna, M. H., et al., Global distribution of crustal magnetization discovered by the Mars Global Surveyor MAG/ER experiment, *Science*, 284, 790–793, 1999.
- Afzal, R. S., Mars Observer Laser Altimeter: Laser transmitter, *Applied Optics*, 33, 3184–3188, 1994.
- Aharonson, O., M. T. Zuber, G. A. Neumann, D. E. Smith, and J. W. Head, Mars: Northern hemisphere slopes and slope distributions, *Geophys. Res. Lett.*, 25, 4413–4416, 1998.
- Aharonson, O., M. T. Zuber, and D. H. Rothman, Statistics of Mars' topography from MOLA: Slopes, correlations and physical models, *J. Geophys. Res.*, this issue, 2001.
- Albee, A. A., F. D. Palluconi, and R. E. Arvidson, Mars Global Surveyor Mission: Overview and status, *Science*, 279, 1671–1672, 1998.
- Albee, A. A., F. D. Palluconi, and R. E. Arvidson, Mars Global Surveyor mapping mission overview, *J. Geophys. Res.*, this issue, 2001.
- Arrell, J. R., Implications of Martian Polar Insolation Levels on the Climatic Cycling of Volatiles, *MSc. Thesis, Massachusetts Institute of Technology*, 2000.
- Baker, V. R., R. G. Strom, V. C. Gulick, J. S. Kargel, G. Komatsu, and V. S. Kale, Ancient oceans, ice sheets, and the hydrological cycle on Mars, *Nature*, 352, 589–594, 1991.
- Bandfield, J. L., V. Hamilton, and P. R. Christensen, A global view of Martian surface composition from MGS-TES, *Science*, 287, 1626–1630, 2000.
- Banerdt, W. B., and M. P. Golombek, Tectonics of the Tharsis regions of Mars: Insights from MGS topography and gravity, *Lunar Planet. Sci. Conf.*, XXXI, Abstract #2038, 2000.
- Banerdt, W. B., and G. A. Neumann, The topography (and ephemeris) of Phobos from MOLA ranging, *Lunar Planet. Sci. Conf.*, XXX, Abstract #2021, 1999.
- Banerdt, W. B., R. J. Phillips, N. H. Sleep, and R. S. Saunders, Thick shell tectonics on one-plate planets: Applications to Mars, *J. Geophys. Res.*, 87, 9723–9733, 1982.
- Banerdt, W. B., M. P. Golombek, and K. L. Tanaka, Stress and tectonics on Mars, in *Mars*, edited by H. H. Kieffer, B. M. Jakosky, C. W. Snyder, and M. S. Matthews, pp. 249–297, Univ. of Ariz. Press, Tucson, 1992.
- Barlow, N. G., and T. L. Bradley, Martian impact craters: Correlations of ejecta and interior morphologies with diameter, latitude, and terrain, *Icarus*, 87, 156–179, 1990.
- Bell, J. F., W. M. Calvin, M. E. Ockert-Bell, D. Crisp, J. B. Pollock, and J. Spencer, Detection and monitoring of H₂O and CO₂ ice clouds on Mars, *J. Geophys. Res.*, 101, 9227–9237, 1996.
- Bell, J. F., M. J. Wolf, T. C. Daley, D. Crisp, P. B. James, S. W. Lee, J. T. Trauger, and R. W. Evans, Near-infrared imaging of Mars from HST: Surface reflectance, photometric properties and implications for MOLA data, *Icarus*, 138, 25–35, 1999.
- Bibring, J., et al., ISM observations of Mars and Phobos: First results, *Proc. Lunar Planet. Sci. Conf.*, 20th, 461–471, 1990.
- Bills, B. G., and A. J. Ferrari, Mars topography harmonics and geophysical implications, *J. Geophys. Res.*, 83, 3497–3508, 1978.
- Bills, B. G., and A. J. Ferrari, Venus topography: A harmonic analysis, *J. Geophys. Res.*, 90, 827–836, 1985.
- Byer, R. L., Diode laser-pumped solid state lasers, *Science*, 239, 742–747, 1988.
- Carr, M. H., *The Surface of Mars*, Yale University Press, New Haven, 1981.
- Carr, M. H., *Water on Mars*, p. 229, Oxford University Press, New York, 1996.
- Carr, M. H., and G. D. Clow, Martian channels and valleys: Their characteristics, distribution and age, *Icarus*, 48, 91–117, 1981.
- Carr, M. H., L. S. Crumpler, J. A. Cutts, R. Greeley, J. E. Guest, and H. Masursky, Martian impact craters and emplacement of ejecta by surface flow, *J. Geophys. Res.*, 82, 4055–4065, 1977.
- Casani, J. R., et al., *Report on the loss of the Mars Polar Lander and Deep Space 2 missions*, p. 154, JPL-D18709, Pasadena, CA, 2000.
- Christensen, P. R., Regional dust deposits on Mars: Physical properties, age, and history, *J. Geophys. Res.*, 91, 3,533–3,545, 1986.
- Christensen, P. R., and H. J. Moore, The Martian surface layer, in *Mars*, edited by H. H. Kieffer, B. M. Jakosky, C. W. Snyder, and M. S. Matthews, pp. 686–729, Univ. of Ariz. Press, Tucson, 1992.
- Christensen, P. R., T. Clancy, H. H. K. V. Hamilton, J. Bandfield, M. C. Malin, B. J. Conrath, J. C. Pearl, and M. D. Smith, Mapping orbit results of the MGS TES investigation, *J. Geophys. Res.*, this issue, 2001.
- Clifford, S. M., A model for the hydrologic and climatic behavior of water on Mars, *J. Geophys. Res.*, 98, 10,973–11,016, 1993.
- Cole, T. D., M. T. Boies, A. F. C. A. S. El-Dinary, M. T. Zuber, and D. E. Smith, The Near Earth Asteroid Rendezvous laser altimeter, *Space Sci. Rev.*, 82, 217–253, 1997.
- Comer, R. P., S. C. Solomon, and J. W. Head, The Olympus Mons paradox: Why hasn't the martian lithosphere failed under the load?, *Lunar Planet. Sci. Conf.*, XI, 171–173, 1981.
- Comer, R. P., S. C. Solomon, and J. W. Head, Mars: Thickness of the lithosphere from the tectonic response to volcanic loads, *Rev. Geophys.*, 23, 61–72, 1985.

- Connerney, J. E. P., et al., Magnetic lineations in the ancient crust of Mars, *Science*, 284, 794–798, 1999.
- Conrath, B. R., Curran, R. Hanel, V. Kunde, W. M. J. Pearl, J. Pirraglia, J. Welker, and T. Burke, Atmospheric and surface properties of Mars obtained by infrared spectroscopy on Mariner 9, *J. Geophys. Res.*, 78, 4267–4278, 1973.
- Conrath, B. R., J. C. Pearl, M. D. Smith, W. C. Maguire, P. C. Christensen, S. Dason, and M. S. Kaerberer, Mars Global Surveyor Thermal Emission Spectrometer (TES): Atmospheric temperatures during aerobraking and science phasing, *J. Geophys. Res.*, 105, 9509–9519, 2000.
- Cutts, J. A., K. R. Blasius, G. A. Briggs, M. H. Carr, R. Greeley, and H. Masursky, North polar region of Mars: Imaging results from Viking 2, *Science*, 194, 1329–1337, 1976.
- Davies, M. E., and F. Y. Katayama, The 1982 control network of Mars, *J. Geophys. Res.*, 88, 7503–7504, 1982.
- Davies, M. E., F. Y. Katayama, and J. A. Roth, Control net of Mars, February 1978, *RAND Rept. R-2309-NASA*, 1978.
- Davies, M. E., V. K. Abalakin, A. Brahic, M. Bursa, B. H. Chovitz, J. H. Lieske, P. K. Seidelmann, A. T. Sinclair, and Y. S. Tjufflin, Report of the IAU/IAG/COSPAR working group on cartographic coordinates and rotational elements of the planets and satellites: 1991, *Cel. Mech. and Dynam. Astron.*, 53, 377–397, 1992a.
- Davies, M. E., R. M. Batson, and S. S. C. Wu, Geodesy and cartography, in *Mars*, edited by H. H. Kieffer, B. M. Jakosky, C. W. Snyder, and M. S. Matthews, pp. 321–342, Univ. of Ariz. Press, Tucson, 1992b.
- Downs, G. S., R. M. Goldstein, R. R. Green, and G. A. Morris, Mars radar observations, a preliminary report, *Science*, 174, 1324–1327, 1971.
- Downs, G. S., P. E. Reichley, and R. R. Green, Radar measurements of Martian topography and surface properties: The 1971 and 1973 oppositions, *Icarus*, 26, 273–312, 1975.
- Downs, G. S., P. E. Reichley, and R. R. Green, Radar studies of the Martian surface at centimeter wavelengths: The 1975 opposition, *Icarus*, 33, 441–453, 1978.
- Downs, G. S., P. J. Mouginis-Mark, S. H. Zisk, and T. W. Thompson, New radar-derived topography for the northern hemisphere of Mars, *J. Geophys. Res.*, 87, 9747–9754, 1982.
- Durham, W. B., S. H. Kirby, and L. S. Stern, Steady-state rheology of solid CO₂: Preliminary results, *Geophys. Res. Lett.*, 26, 3493–3496, 1999.
- Duxbury, T. C., The figure of Phobos, *Icarus*, 78, 169–180, 1989.
- Duxbury, T. C., Preliminary cartographic analysis of the Pathfinder landing site using Viking Orbiter images, in *Mars Pathfinder Landing Site Workshop II: Characteristics of the Ares Vallis region and field trips in the channeled scabland*, Washington, edited by M. P. Golombek, K. S. Edgett, and J. W. R. Jr., vol. LPI Tech. Report 95-01, Part 2, pp. 35–36, Lunar and Planetary Institute, 1995.
- Duxbury, T. C., An improved geodetic grid for Mars from the Mars Orbiter Laser Altimeter (MOLA), *Jet Propulsion Laboratory, Report of the Mars Geodesy and Cartography Working Group*, 2000.
- Eliason, E., A. McEwen, A. Allison, R. Batson, L. Soderblom, and M. Martin, Introduction to the Mars Mosaicked Digital Model (MDIM) CDROM volumes, *U.S.G.S. Tech. Rept.*, 1992.
- Esposito, P. B., W. B. Banerdt, G. F. Lindal, W. L. Sjogren, M. A. Slade, B. G. Bills, D. E. Smith, and G. Balmino, Gravity and topography, in *Mars*, edited by H. H. Kieffer, B. M. Jakosky, C. W. Snyder, and M. S. Matthews, pp. 209–248, Univ. of Ariz. Press, Tucson, 1992.
- Fishbaugh, K. E., and J. W. Head, North polar region of Mars: Topography of circumpolar deposits from Mars Orbiter Laser Altimeter (MOLA) data and evidence for asymmetric retreat of the polar cap, *J. Geophys. Res.*, 105, 22,455–22,486, 2000.
- Folkner, W. M., C. F. Yoder, D. N. Yuan, and R. A. P. E. M. Standish, Interior structure and seasonal mass redistribution of Mars from radio tracking of Mars Pathfinder, *Science*, 178, 1749–1751, 1997.
- Forget, F., G. B. Hansen, and J. B. Pollack, Low brightness temperatures of Martian polar caps: CO₂ clouds or low surface emissivity?, *J. Geophys. Res.*, 100, 21,219–21,234, 1995.
- Frey, H., S. E. Sakimoto, and J. H. Roark, The MOLA topographic signature of the crustal dichotomy boundary zone on Mars, *Geophys. Res. Lett.*, 25, 4409–4412, 1998.
- Frey, H., S. E. H. Sakimoto, and J. H. Roark, Discovery of a 450-km-diameter, multiring basin on Mars through analysis of MOLA topographic data, *Geophys. Res. Lett.*, 26, 1657–1660, 1999.
- Frey, H., L. Hutchinson, S. E. H. Sakimoto, and J. H. Roark, A large population of possible buried impact basins on Mars revealed by MOLA topographic data, *Lunar Planet. Sci. Conf.*, XXXI, Abstract #1736, 2000a.
- Frey, H., J. H. Roark, and S. E. H. Sakimoto, Detailed topographic structure of the Isidis impact basin from MOLA data, *Lunar Planet. Sci. Conf.*, XXXI, Abstract #1748, 2000b.
- Frey, H. V., and R. A. Schultz, Large impact basins and the megaimpact origin for the crustal dichotomy on Mars, *Geophys. Res. Lett.*, 15, 229–232, 1988.
- G. A. Neumann, D. E. S., and M. T. Zuber, Clouds detected by the Mars Orbiter Laser Altimeter after one Mars year, *J. Geophys. Res.*, submitted, 2001.
- Gardner, C. S., Target signatures for laser altimeters: An analysis, *Appl. Optics*, 21, 448–453, 1982.
- Gardner, C. S., Ranging performance of satellite laser altimeters, *IEEE Trans. Geosci. Rem. Sens.*, 30, 1061–1072, 1992.
- Garvin, J. B., J. L. Bufton, J. B. Blair, D. Harding, S. B. Luthcke, J. J. Frawley, and D. D. Rowlands, Observations of the Earth's topography from the Shuttle Laser Altimeter (SLA): Laser pulse echo recovery measurements of terrestrial surfaces, *Phys. Chem. Earth*, 23, 1053–1068, 1998.
- Garvin, J. B., J. J. Frawley, and J. B. Abshire, Vertical roughness of Mars from the Mars Orbiter Laser Altimeter, *Geophys. Res. Lett.*, 26, 181–184, 1999.
- Garvin, J. B., S. E. Sakimoto, J. J. Frawley, and C. Schnetzler, Geometric properties of Martian impact craters: An assessment from the Mars Orbiter Laser Altimeter (MOLA) digital elevation modes, *Lunar Planet. Sci. Conf.*, XXXI, Abstract #1619, 2000a.
- Garvin, J. B., S. E. H. Sakimoto, J. J. Frawley, and C. Schnetzler, North polar region craterforms on Mars: Geometric characteristics from the Mars Orbiter Laser Altimeter, *Icarus*, 144, 329–352, 2000b.

- Garvin, J. B., S. E. H. Sakimoto, J. J. Frawley, C. C. Schnetzler, and H. M. Wright, Topographic evidence for geologically recent near-polar volcanism on Mars, *Icarus*, **145**, 648–652, 2000c.
- Geirasch, P. J., and R. Goody, A study of the thermal and dynamical structure of the Martian lower atmosphere, *Planet. Space Sci.*, **16**, 615–646, 1968.
- Goldstein, R. M., W. G. Melbourne, G. A. Morris, G. S. Downs, and D. A. O'Handley, Preliminary radar results of Mars, *Radio Sci.*, **70**, 475–478, 1970.
- Golombek, M. P., K. L. Tanaka, and B. J. Franklin, Extension across Tempe Terra, Mars, from measurements of fault scarp widths and deformed craters, *J. Geophys. Res.*, **101**, 26,119–26,130, 1996.
- Golombek, M. P., R. A. Cook, H. J. Moore, and T. J. Parker, Selection of the Mars Pathfinder landing site, *J. Geophys. Res.*, **102**, 3967–3988, 1997a.
- Golombek, M. P., F. S. Anderson, and M. T. Zuber, Martian wrinkle ridge topography: Evidence for subsurface faults from MOLA, *J. Geophys. Res.*, *this issue*, 2001.
- Golombek, M. P., et al., Overview of the Mars Pathfinder mission and assessment of landing site predictions, *Science*, **278**, 1743–1748, 1997b.
- Greeley, R., and J. E. Guest, Geologic map of the eastern equatorial region of Mars, Scale 1:15,000,000, *U.S. Geol. Survey Map I-1802-B*, 1987.
- Greeley, R., and P. D. Spudis, Volcanism on Mars, *Rev. Geophys.*, **19**, 13–41, 1981.
- Hapke, B., R. Nelson, and W. Smythe, The opposition effect of the Moon: Coherent backscatter and shadow hiding, *Icarus*, **133**, 89–97, 1998.
- Harmon, J. K., and S. J. Ostro, Dual-polarization radar observations with extended coverage, *Icarus*, **62**, 110–128, 1985.
- Harmon, J. K., D. B. Campbell, and S. J. Ostro, Dual-polarization radar observations of Mars: Tharsis and environs, *Icarus*, **52**, 171–187, 1982.
- Harrington, B., R. J. Phillips, and M. P. Golombek, Extension across Tempe Terra. Mars from MOLA topographic measurements, *Fifth Int. Conf. on Mars, Abstract #6130*, 1999.
- Head, J. W., Detection of lava flow unit thicknesses and characteristics on Mars: First results from Mars Orbiter Laser Altimeter (MOLA) data, *Lunar Planet. Sci. Conf.*, **XXIX**, Abstract #1324, 1998.
- Head, J. W., Extensive south polar cap in middle Mars history? Tests using MOLA data, *Lunar Planet. Sci. Conf.*, **XXX**, Abstract #1119, 2000.
- Head, J. W., M. Kreslavsky, H. Hiesinger, M. Ivanov, S. Pratt, N. Seibert, D. E. Smith, and M. T. Zuber, Oceans in the past history of Mars: Tests for their presence using Mars Orbiter Laser Altimeter (MOLA) data, *Geophys. Res. Lett.*, **25**, 4401–4404, 1998a.
- Head, J. W., N. Seibert, S. Pratt, D. Smith, M. Zuber, J. B. Garvin, P. J. McGovern, and the MOLA Science Team, Volcanic calderas on Mars: Initial views using Mars Orbiter Laser Altimeter (MOLA) data, *Lunar Planet. Sci. Conf.*, **XXIX**, Abstract #1488, 1998b.
- Head, J. W., N. Seibert, S. Pratt, D. Smith, M. Zuber, S. Solomon, P. J. McGovern, J. B. Garvin, and the MOLA Science Team, Characterization of major volcanic edifices on Mars using Mars Orbiter Laser Altimeter (MOLA) data, *Lunar Planet. Sci. Conf.*, **XXIX**, Abstract #1322, 1998c.
- Head, J. W., H. Hiesinger, M. A. Ivanov, M. A. Kreslavsky, S. Pratt, and B. J. Thomson, Possible oceans on Mars: Evidence from Mars Orbiter Laser Altimeter data, *Science*, **286**, 2134–2137, 1999.
- Head, J. W., et al., Oceans in the past history of Mars: Tests for their presence using Mars Orbiter Laser Altimeter (MOLA) data, *J. Geophys. Res.*, **98**, 17,149–17,181, 1998d.
- Hiesinger, H., and J. W. Head, Characteristics and origin of polygonal terrain in southern Utopia, Mars: Preliminary results from the Mars Orbiter laser Altimeter (MOLA) and Mars Orbiter Camera (MOC) data, *J. Geophys. Res.*, **105**, 11,999–12,022, 2000.
- Hinson, D. P., R. A. Simpson, J. D. Twicken, and G. L. Tyler, Cinitial results from radio occultation measurements with Mars Global Surveyor, *J. Geophys. Res.*, **104**, 26,997–27,012, 1999.
- Hord, C. W., Mariner 6 and 7 ultraviolet spectrometer experiment: Photometry and topography of Mars, *Icarus*, **17**, 443–456, 1972.
- Hulme, G., The interpretation of lava flow morphology, *Geophys. J. R. Astron. Soc.*, **39**, 361–383, 1974.
- Hynek, B., and R. J. Phillips, Evidence for extensive denudation of the Martian highlands, *Geology*, p. in press, 2001.
- Ivanov, A. B., *Some aspects of the Martian climate from the Mars Orbiter Laser Altimeter Investigation*, Ph.D. Thesis, California Institute of Technology, Pasadena, CA, 2000.
- Ivanov, A. B., and D. O. Muhleman, Opacity of the Martian atmosphere from Mars Orbiter Laser Altimeter (MOLA) observations, *Geophys. Res. Lett.*, **25**, 4417–4420, 1998.
- Ivanov, A. B., and D. O. Muhleman, The role of sublimation for the formation of the northern ice cap: Results from the Mars Orbiter Laser Altimeter, *Icarus*, **144**, 436–448, 2000.
- Jager, K. M., J. W. Head, B. J. Thomson, P. J. McGovern, and S. C. Solomon, Alba Patera, Mars: Characterization using Mars Orbiter Laser Altimeter (MOLA) data and comparison with other volcanic edifices, *Lunar Planet. Sci. Conf.*, **XXX**, Abstract #1915, 1999.
- Johnson, C. L., S. C. Solomon, J. W. Head, R. J. Phillips, D. E. Smith, and M. T. Zuber, Lithospheric loading by the north polar cap of Mars, *Icarus*, **144**, 313–328, 2000.
- Kargel, J. S., and R. G. Strom, Ancient glaciation on Mars, *Geology*, **20**, 3–7, 1992.
- Kieffer, H. H., T. Z. Martin, A. R. Peterfreund, B. M. Jakosky, E. M. Miner, and F. D. Palluconi, Thermal and albedo mapping of Mars during the Viking primary mission, *J. Geophys. Res.*, **12**, 4249–4291, 1977.
- Kieffer, H. H., P. A. Davis, and L. A. Soderblom, Mars' global properties: Maps and applications, *Proc. Lunar Planet. Sci. Conf.*, **12**, 1395–1417, 1981.
- Kieffer, H. H., B. M. Jakosky, and C. W. Snyder, The planet Mars: From antiquity to present, in *Mars*, edited by H. H. Kieffer, B. M. Jakosky, C. W. Snyder, and M. S. Matthews, pp. 1–33, Univ. of Ariz. Press, Tucson, 1992.
- Klassen, D. R., J. F. Bell, R. R. Howell, P. E. Johnson, W. Golisch, C. D. Kaminski, and D. Griep, Infrared spectral imaging of Martian clouds and ices, *Icarus*, **138**, 36–48, 1999.

- Kliore, A. J., D. L. Cain, G. S. Levy, V. R. Eshleman, G. Fjeldbo, and F. D. Drake, Occultation experiment: Results of the first direct measurement of Mars' atmosphere and ionosphere, *Science*, 149, 1243–1248, 1965.
- Kliore, A. J., D. L. Cain, G. Fjeldbo, B. L. Seidel, and M. J. Sykes, The atmosphere of Mars from Mariner 9 radio occultation measurements, *Icarus*, 17, 484–516, 1972.
- Kliore, A. J., F. J. Fjeldbo, B. L. Seidel, M. J. Sykes, and P. M. Woiceshyn, S-band radio occultation measurements of the atmosphere and topography of Mars with Mariner 9: Extended mission coverage of the polar and intermediate latitudes, *J. Geophys. Res.*, 78, 4331–4351, 1973.
- Komar, P. D., Comparisons of the hydraulics of water flows in Martian outflow channels with flows of similar scale on Earth, *Icarus*, 37, 156–181, 1979.
- Komatsu, G., and V. R. Baker, Paleohydrology and flood geomorphology of Ares Vallis, *J. Geophys. Res.*, 102, 4151–4160, 1997.
- Kreslavsky, M. A., and J. W. Head, Kilometer-scale slopes on Mars and their correlation with geologic units: Initial results from Mars Orbiter Laser Altimeter (MOLA) data, *J. Geophys. Res.*, 104, 21,911–21,924, 1999.
- Kreslavsky, M. A., and J. W. Head, Kilometer-scale roughness of Mars: Results from MOLA data analysis, *J. Geophys. Res.*, 101, 26,695–16,711, 2000.
- Lemoine, F. G., D. D. Rowlands, D. E. Smith, D. S. Chinn, D. E. Pavlis, S. B. Luthcke, G. A. Neumann, and M. T. Zuber, Orbit determination for Mars Global Surveyor during mapping, *AIAA*, pp. 99–328, 1999.
- Lemoine, F. G., D. D. Rowlands, D. E. Smith, D. S. Chinn, D. E. Pavlis, S. B. Luthcke, G. A. Neumann, and M. T. Zuber, Gravity field of Mars from Mars Global Surveyor, *J. Geophys. Res.*, this issue, 2001.
- Leovy, C. B., and Y. Mintz, Numerical simulation of the atmospheric circulation and climate of Mars, *J. Atmos. Sci.*, 26, 1167–1190, 1969.
- Lindal, G. F., H. B. Hotz, D. N. Sweetnam, Z. Shippony, J. P. Brenkle, G. V. Hartsell, R. T. Spear, and W. H. J. Michael, Viking radio occultation measurements of the atmosphere and topography of Mars: Data acquired during 1 Martian year of tracking, *J. Geophys. Res.*, 84, 8443–8456, 1979.
- Lingenfelter, R. E., and G. Schubert, Evidence for convection in planetary interiors from first-order topography, *Moon*, 7, 172–180, 1973.
- Lorell, J., et al., Gravity field of Mars from Mariner 9 tracking data, *Icarus*, 18, 304–316, 1973.
- Malin, M. C., and K. S. Edgett, Oceans or seas in the Martian northern lowlands: High-resolution imaging tests of proposed coastlines, *Geophys. Res. Lett.*, 26, 3049–3052, 1999.
- Malin, M. C., and K. S. Edgett, Evidence for recent groundwater seepage and surface runoff on Mars, *Science*, 288, 2330–2335, 2000.
- Malin, M. C., et al., Early views of the Martian surface from the Mars Orbiter Camera of Mars Global Surveyor, *Science*, 279, 1681–1685, 1998.
- Marshall, J. A., N. P. Zelensky, S. M. Klosko, D. S. Chinn, S. B. Luthcke, K. E. Rachlin, and R. G. Williamson, The temporal and spatial characteristics of TOPEX/POSEIDON radial orbit error, *J. Geophys. Res.*, 100, 25,331–25,352, 1995.
- McCarthy, J. J., S. Rowton, D. Moore, S. Luthcke, D. E. Pavlis, L. S. Tsoussi, D. D. Rowlands, and J. A. Marshall, Geodyn systems descriptions and operations manuals, *NASA/GSFC and Hughes-STX Contractor Report*, 1994.
- McEwen, A. S., M. C. Malin, L. Keszthelyi, P. Lanagan, R. Beyer, and W. K. Hartmann, Recent and ancient flood lavas on Mars, *Lunar Planet. Sci. Conf.*, XXX, Abstract #1829, 1999.
- McGarry, J. F., L. K. Pacini, J. B. Abshire, and J. B. Blair, Design and performance of an autonomous tracking for the Mars Observer Laser Altimeter, *Conf. on Lasers and Electro-Optics*, 10, CThR27, 1991.
- McGill, G. E., Buried topography of Utopia, Mars: Persistence of a giant impact depression, *J. Geophys. Res.*, 94, 2753–2759, 1989.
- McGovern, P. J., and S. C. Solomon, State of stress, faulting, and eruption characteristics of large volcanoes on Mars, *J. Geophys. Res.*, 98, 23,553–23,579, 1993.
- McGovern, P. J., and S. C. Solomon, Filling of flexural moats around large volcanoes on Venus: Implications for volcano structure and global magmatic flux, *J. Geophys. Res.*, 102, 16,303–16,318, 1997.
- McGovern, P. J., S. C. Solomon, J. W. Head, D. E. Smith, M. T. Zuber, and G. A. Neumann, Extension and uplift at Alba Patera: Insights from MOLA observations and loading models, *J. Geophys. Res.*, this issue, 2001.
- Melosh, H. J., *Impact Cratering: A Geologic Process*, Oxford Univ. Press, New York, 1989.
- Montesi, L. G. J., and M. T. Zuber, The lithospheric structure of the margin of Tharsis as indicated by wrinkle ridges, *Tharsis Workshop*, 2000.
- Mustard, J. F., S. Erard, J.-P. Bibring, J. W. Head, S. Hurez, Y. Langevin, C. M. Pieters, and C. J. Sotin, The surface of Syrtis Major: Composition of the volcanic substrate and mixing with altered dust and soil, *J. Geophys. Res.*, 98, 3387–3400, 1993.
- Mutch, T. A., R. E. Arvidson, J. W. Head, K. L. Jones, and R. S. Saunders, *The Geology of Mars*, Princeton University Press, Princeton, 1976.
- Neumann, G. A., F. G. Lemoine, and D. D. Rowlands, Crossover analysis in MOLA data processing, *J. Geophys. Res.*, this issue, 2001.
- Nye, J. F., W. B. Durham, P. M. Schenk, and J. M. Moore, The instability of a south polar cap on Mars composed of carbon dioxide, *Icarus*, 144, 449–455, 2000.
- Paige, D. A., and K. D. Keegan, Thermal and albedo mapping of the polar regions of Mars using Viking thermal mapper observations 2. South polar region, *J. Geophys. Res.*, 99, 25,993–26,013, 1994.
- Paige, D. A., J. E. Bachman, and K. D. Keegan, Thermal and albedo mapping of the polar regions of Mars using Viking thermal mapper observations 1. North polar region, *J. Geophys. Res.*, 99, 25,959–25,991, 1994.
- Parker, T. J., D. S. Gorsline, R. S. Saunders, and D. M. Schneeberger, Coastal geomorphology of the Martian northern plains, *J. Geophys. Res.*, 98, 11,061–11,078, 1993.
- Pettengill, G. H., and P. G. Ford, Winter clouds over the north Martian polar cap, *Geophys. Res. Lett.*, 27, 609–612, 2000.
- Pettengill, G. H., C. C. Counselman, L. P. Rainville, and I. I. Shapiro, Radar measurements of Martian topography, *Astron. J.*, 74, 461–482, 1969.

- Pettengill, G. H., A. A. E. Rogers, and I. I. Shapiro, Martian craters and a scarp as seen by radar, *Science*, 174, 1321–1324, 1971.
- Pettengill, G. H., I. I. Shapiro, and A. A. E. Rogers, Topography and radar scattering properties of Mars, *Icarus*, 18, 22–28, 1973.
- Phillips, R. J., M. T. Zuber, S. A. Hauck, R. M. Williams, and K. B. Portle, Why is there a negative gravity ring around Tharsis on Mars?, *Lunar Plant. Sci. Conf.*, XXXI, Abstract #1303, 2000.
- Phillips, R. J., et al., Ancient geodynamics and global-scale hydrology on Mars, *Science*, in press, 2001.
- Pike, R. J., Control of crater morphology by gravity and target type: Mars, Earth, Moon, *Proc. Lunar Plant. Sci. Conf.*, 11, 2159–2189, 2000.
- Plaut, J. J., R. Kahn, E. A. Guinness, and R. E. Arvidson, Accumulation of sedimentary debris in the south polar region of Mars and implication for climate history, *Icarus*, 75, 357–377, 1988.
- Plescia, J. B., and M. P. Golombek, Origin of planetary wrinkle ridges based on the study of terrestrial analogs, *Geol. Soc. Am. Bull.*, 97, 1289–1299, 1986.
- Pollack, J. B., R. M. Haberle, and J. Schaeffer, Simulations of the general circulation of the Martian atmosphere 1. Polar processes, *J. Geophys. Res.*, 95, 1447–1473, 1990.
- Ramos-Izquierdo, L., J. L. Bufton, and P. Hayes, Optical system design and integration of the Mars Observer Laser Altimeter, *Appl. Opt.*, 133, 307–322, 1994.
- Rogers, A. E. E., M. E. Ash, C. C. Counselman, I. I. Shapiro, and G. H. Pettengill, Radar measurements of the surface topography and roughness of Mars, *Radio Sci.*, 5, 465–473, 1970.
- Roth, L. E., G. S. Downs, R. S. Saunders, and G. Schubert, Radar altimetry of south Tharsis, Mars, *Icarus*, 42, 287–316, 1980.
- Rowlands, D. D., J. A. Marshall, J. J. McCarthy, S. C. Rowton, D. Moore, D. E. Pavlis, and S. B. Lutchke, Geodyn II system description, *Hughes-STX Contractor Report, Greenbelt, MD*, 1993.
- Rowlands, D. D., D. E. Pavlis, F. G. Lemoine, G. A. Neumann, and S. B. Lutchke, The use of crossover constraint equations derived from laser altimetry in the orbit determination of Mars Global Surveyor, *Geophys. Res. Lett.*, 26, 1191–1194, 1999.
- Sakimoto, S. E. H., and J. B. Garvin, Topography of impact craters on the northern polar cap of Mars, *Lunar Planet. Sci. Conf.*, XXX, 1999.
- Schubert, G., and T. Spohn, Thermal history of Mars and the sulfur content of its core, *J. Geophys. Res.*, 95, 14,095–14,104, 1990.
- Schubert, G., and T. Spohn, Thermal convection in a volumetrically heated, infinite Prandtl number fluid with strongly temperature-dependent viscosity: Implications for planetary thermal evolution, *J. Geophys. Res.*, 103, 18,171–18,181, 1998.
- Schultz, R. A., and H. V. Frey, A new survey of multiring basins on Mars, *J. Geophys. Res.*, 95, 14,175–14,189, 1990.
- Schultz, R. A., and K. L. Tanaka, Lithospheric-scale buckling and thrust structures on Mars: The Coprates rise and south Tharsis ridge belt, *J. Geophys. Res.*, 99, 8371–8385, 1994.
- Scott, D. H., and K. L. Tanaka, Geologic map of the western equatorial region of Mars, Scale 1:15,000,000, *U.S. Geol. Survey Map I-1802-A*, 1986.
- Sengor, A. M. C., and K. Burke, Relative timing of rifting and volcanism on earth and its tectonic implications, *Geophys. Res. Lett.*, 5, 419–421, 1978.
- Sharp, R. P., Mars: Fretted and chaotic terrains, *J. Geophys. Res.*, 78, 4073–4083, 1973.
- Sharp, R. P., L. A. Soderblom, B. C. Murray, and J. A. Cutts, More on the dichotomy boundary, *J. Geophys. Res.*, 76, 331–341, 1971.
- Shum, C. K., B. H. Zhang, B. E. Schutz, and B. D. Tapley, Altimeter crossover methods for precision orbit determination and the mapping of geophysical parameters, *J. Astronaut. Sci.*, 38, 355–368, 1990.
- Simons, F. J., M. T. Zuber, and J. Korenaga, Isostatic response of the Australian lithosphere: Estimation of effective elastic thickness and anisotropy using multitaper spectral analysis, *J. Geophys. Res.*, 105, 19,163–19,184, 2000.
- Simons, M. A., S. C. Solomon, and B. H. Hager, Localization of gravity and topography: Constraints on the tectonics and mantle dynamics of Venus, *Geophys. J. Int.*, 131, 24–44, 1997.
- Simpson, R. A., J. K. Harmon, S. H. Zisk, T. W. Thompson, and D. O. Muhleman, Radar determination of Mars surface properties, in *Mars*, edited by H. H. Kieffer, B. M. Jakosky, C. W. Snyder, and M. S. Matthews, pp. 652–685, Univ. of Ariz. Press, Tucson, 1992.
- Sleep, N. H., Martian plate tectonics, *J. Geophys. Res.*, 99, 5639–5655, 1994.
- Sleep, N. H., and R. J. Phillips, Gravity and lithospheric stress on the terrestrial planets with reference to the Tharsis region on Mars, *J. Geophys. Res.*, 90, 4469–4489, 1985.
- Smith, D. E., and M. T. Zuber, The shape of Mars and the topographic signature of the hemispheric dichotomy, *Science*, 271, 184–188, 1996.
- Smith, D. E., and M. T. Zuber, The relationship between MOLA northern hemisphere topography and the 6.1-mbar atmospheric pressure surface of Mars, *Geophys. Res. Lett.*, 25, 4297–4400, 1998.
- Smith, D. E., M. T. Zuber, G. A. Neumann, and F. G. Lemoine, Topography of the Moon from the Clementine lidar, *J. Geophys. Res.*, 102, 1591–1611, 1997.
- Smith, D. E., W. L. Sjogren, G. L. Tyler, G. Balmino, F. G. Lemoine, and A. S. Konopliv, The gravity field of Mars: Results from Mars Global Surveyor, *Science*, 286, 94–96, 1999a.
- Smith, D. E., et al., Topography of the northern hemisphere of Mars from the Mars Orbiter Laser Altimeter (MOLA), *Science*, 279, 1686–1692, 1998.
- Smith, D. E., et al., The global topography of Mars and implications for surface evolution, *Science*, 284, 1495–1503, 1999b.
- Smith, M. D., J. C. Pearl, B. J. Conrath, and P. R. Christensen, Mars Global Surveyor Thermal Emission Spectrometer (TES) observations of dust opacity during aerobraking and science phasing, *J. Geophys. Res.*, 105, 9539–9552, 2000.
- Smith, W. H. F., and P. Wessel, Gridding with continuous curvature splines in tension, *Geophys.*, 55, 293–305, 1990.
- Soderblom, L. A., The composition and surface mineralogy of the Martian surface from spectroscopic observations: 0.3 μm to 50 μm , in *Mars*, edited by H. H. Kieffer, B. M. Jakosky, C. W. Snyder, and M. S. Matthews, pp. 557–593, Univ. of Ariz. Press, Tucson, 1992.
- Soderblom, L. A., and D. B. Wenner, Possible fossil H₂O liquid-ice interfaces in the Martian crust, *Icarus*, 34, 622–637, 1978.

- Sohl, F., and T. Spohn, The interior structure of Mars: Implications from SNC meteorites, *J. Geophys. Res.*, 102, 1613–1635, 1997.
- Solomon, S. C., and J. W. Head, Evolution of the Tharsis province of Mars: The importance of heterogeneous lithospheric thickness and volcanic construction, *J. Geophys. Res.*, 82, 9755–9774, 1981.
- Solomon, S. C., and J. W. Head, Heterogeneities in the thickness of the elastic thickness of Mars: Constraints on heat flow and internal dynamics, *J. Geophys. Res.*, 95, 11,073–11,083, 1990.
- Solomon, S. C., C. L. Johnson, P. J. McGovern, O. Aharonson, W. B. Banerdt, J. W. Head, R. J. Phillips, and M. T. Zuber, An overview of lithospheric flexure on Mars: Implications of initial MOLA observations, *Lunar and Planet. Sci. Conf.*, XXIX, Abstract #1389, 1998.
- Spudis, P. D., R. A. Riese, and J. G. Gillis, Ancient multiring basins on the Moon revealed by Clementine laser altimetry, *Science*, 266, 1848–1851, 1994.
- Standish, E. M., X. X. Newhall, J. G. Williams, and W. M. Folkner, Jpl Planetary and Lunar Ephemerides, DE403/LE403, *JPL Report*, IOM 314.10-127, 1995.
- Stewart, E. M., and J. W. Head, Ancient Martian volcanoes in the Aeolis region: New evidence from MOLA data, *J. Geophys. Res.*, in press, 2001.
- Sun, X., F. M. Davidson, L. Boutsikais, and J. B. Abshire, Receiver characteristics of laser altimeters with avalanche photodiode, *IEEE Trans. Aerosp. Electron. Syst.*, 28, 268–274, 1992.
- Tanaka, K. L., M. P. Golombek, and W. B. Banerdt, Reconciliation of the stress and structural histories of the Tharsis region, Mars, *J. Geophys. Res.*, 96, 15,617–15,633, 1991.
- Tanaka, K. L., D. K. Scott, and R. Greeley, Global stratigraphy, in *Mars*, edited by H. H. Kieffer, B. M. Jakosky, C. W. Snyder, and M. S. Matthews, pp. 345–382, Univ. of Ariz. Press, Tucson, 1992.
- Tapley, B. D., and G. W. Rosborough, Geographically correlated orbit error and its effect on satellite altimeter missions, *J. Geophys. Res.*, 90, 11,817–11,831, 1985.
- Thomas, P. C., et al., North-south geological differences between the residual polar caps on Mars, *Nature*, 404, 161–164, 2000.
- Thomson, B. J., and J. W. Head, Estimating the silica content of Martian lava flows using MOLA, *Lunar Planet. Sci. Conf.*, XXXI, Abstract #1883, 2000.
- Turcotte, D. L., R. J. Willemann, W. F. Haxby, and J. Norberry, Role of membrane stresses in support of planetary topography, *J. Geophys. Res.*, 86, 3951–3959, 1981.
- Tyler, G. L., G. Balmino, D. P. Hinson, W. L. Sjogren, D. E. Smith, R. A. Simpson, S. W. Asmar, P. Priest, and J. D. Twicken, Radio science observations with Mars Global Surveyor: Orbit insertion through one year in mapping orbit, *J. Geophys. Res.*, this issue, 2001.
- Tyler, G. L., et al., Radio science investigations with Mars Observer, *J. Geophys. Res.*, 97, 7759–7779, 1992.
- Vasavada, A. R., and K. E. Herkenhoff, Polar layered deposits and polar landing sites, *Fifth Int. Conf. on Mars*, Abstract #6086, 1999.
- Ward, W. R., Climatic variations on Mars, *J. Geophys. Res.*, 79, 3375–3386, 1974.
- Watters, T. R., Compressional tectonism on Mars, *J. Geophys. Res.*, 98, 17,049–17,060, 1993.
- Watts, A. B., J. H. Bodine, and M. S. Steckler, Observations of flexure and the state of stress in the oceanic lithosphere, *J. Geophys. Res.*, 85, 5369–6376, 1980.
- Wichman, R. W., and P. H. Schultz, Sequence and mechanisms of deformation around the Hellas and Isidis impact basins on Mars, *J. Geophys. Res.*, 94, 17,333–17,357, 1989.
- Wilhelms, D. E., and S. W. Squyres, The Martian hemispheric dichotomy may be due to a giant impact, *Nature*, 309, 138–140, 1984.
- Williams, K. K., and M. T. Zuber, Measurement and analysis of lunar basin depths from Clementine altimetry, *Icarus*, 131, 107–122, 1998.
- Williams, R. M., Examination of Martian outflow channels and valley network morphology using mars orbiter laser altimeter (MOLA), *Ph.D. Thesis*, Washington University, 2000.
- Williams, R. M., R. J. Phillips, and M. C. Malin, Flow rates and duration within Kasei Valles, Mars: Implications for the formation of a martian ocean, *Geophys. Res. Lett.*, 27, 1073–1076, 2000.
- Wilson, L., and J. W. Head, Review and analysis of volcanic eruption theory and relationships of observed landforms, *Rev. Geophys.*, 19, 221–264, 1994.
- Wise, D. U., M. P. Golombek, and G. E. McGill, Tharsis province of Mars: Geologic sequence, geometry, and a deformation mechanism, *Icarus*, 35, 456–472, 1979a.
- Wise, D. U., M. P. Golombek, and G. E. McGill, Tectonic evolution of Mars, *J. Geophys. Res.*, 84, 7934–7939, 1979b.
- Wu, P., and W. R. Peltier, Pleistocene glaciation and the Earth's rotation: A new analysis, *Geophys. J. R. Astron. Soc.*, 76, 753–791, 1984.
- Wu, S. S. C., Topographic maps of the polar, western, and eastern regions of Mars, scale 1:15,000,000, *U.S. Geol. Survey Map I-2160*, 1991.
- Wu, S. S. C., and F. J. Schaefer, Mars control network: American Society of Photogrammetry, *Proc. 50th Annual Meeting*, pp. 456–464, 1984.
- Yuan, D. N., W. L. Sjogren, A. S. Konopliv, and A. B. Kucinskis, The gravity field of Mars: A 75th degree and order model, *J. Geophys. Res.*, this issue, 2001.
- Zeitler, W., and J. Oberst, The Mars Pathfinder landing site and the Viking control point network, *J. Geophys. Res.*, 104, 8935–8941, 1999.
- Zhong, S., and M. T. Zuber, Degree one mantle convection and the crustal dichotomy on Mars, *Lunar Planet. Sci. Conf.*, XXXI, Abstract #1265, 2000.
- Zuber, M. T., Wrinkle ridges, reverse faulting, and the depth penetration of lithospheric strain in Lunae Planum, Mars, *Icarus*, 114, 81–92, 1995.
- Zuber, M. T., and D. E. Smith, Mars without Tharsis, *J. Geophys. Res.*, 102, 28,673–28,685, 1997.
- Zuber, M. T., D. E. Smith, S. C. Solomon, D. O. Muhleman, J. W. Head, J. B. Garvin, J. B. Abshire, and J. L. Bufton, The Mars Observer Laser Altimeter investigation, *J. Geophys. Res.*, 97, 7781–7797, 1992.
- Zuber, M. T., D. E. Smith, F. G. Lemoine, and G. A. Neumann, The shape and internal structure of the Moon from the Clementine mission, *Science*, 266, 1839–1843, 1994.

- Zuber, M. T., D. E. Smith, A. F. Cheng, and T. D. Cole, The NEAR laser ranging investigation, *J. Geophys. Res.*, 102, 23,761–23,773, 1997.
- Zuber, M. T., L. Lim, and H. J. Zwally, The role of viscous deformation on the morphology of the Martian north polar cap, in *First Int. Conf. on Mars Polar Science and Exploration*, edited by S. Clifford, D. Fisher, and J. Rice, pp. 45–46, Lunar Planet. Inst., Houston, 1998a.
- Zuber, M. T., D. E. Smith, R. J. Phillips, S. C. Solomon, W. B. Banerdt, G. A. Neumann, and O. Aharonson, Shape of the northern hemisphere of Mars from the Mars Orbiter Laser Altimeter (MOLA), *Geophys. Res. Lett.*, 25, 4393–4396, 1998b.
- Zuber, M. T., et al., Observations of the north polar region of Mars from the Mars Orbiter Laser Altimeter, *Science*, 282, 2053–2060, 1998c.
- Zuber, M. T., et al., Internal structure and early thermal evolution of Mars from Mars Global Surveyor topography and gravity, *Science*, 287, 1788–1793, 2000a.
- Zuber, M. T., et al., The shape of asteroid 433 Eros from the NEAR-Shoemaker Laser Rangefinder, *Science*, 289, 2097–2101, 2000b.
- Zurek, R. W., J. R. Barnes, R. M. Haberle, J. B. Pollack, J. E. Tillman, and C. B. Leovy, Dynamics of the atmosphere of Mars, in *Mars*, edited by H. H. Kieffer, B. M. Jakosky, C. W. Snyder, and M. S. Matthews, pp. 835–933, Univ. of Ariz. Press, Tucson, 1992.
- Zwally, H. J., and J. L. Saba, Driving stresses in Mars' polar ice caps and conditions for ice flow, *Fifth Int. Conf. on Mars, Abstract #6151*, 1999.
- J. B. Abshire, R. S. Afzal, H. V. Frey, F. G. Lemoine, G. A. Neumann, D. D. Rowlands, D. E. Smith, X. Sun, Laboratory for Terrestrial Physics, Code 920, NASA/Goddard Space Flight Center, Greenbelt, MD 20771 (e-mail: dsmith@tharsis.gsfc.nasa.gov, James.Abshire@gsfc.nasa.gov, Robert.Afzal@gsfc.nasa.gov, frey@denali.gsfc.nasa.gov, flemoine@ares.gsfc.nasa.gov, neumann@tharsis.gsfc.nasa.gov, drowland@helmert.gsfc.nasa.gov)
- O. Aharonson, M. T. Zuber, Department of Earth, Atmospheric, and Planetary Sciences, Massachusetts Institute of Technology, Building 54, 77 Massachusetts Avenue, Cambridge, MA 02139-4307 (e-mail: oded@mit.edu, zuber@mit.edu)
- W. B. Banerdt, T. C. Duxbury, M. P. Golombek, A. B. Ivanov, Jet Propulsion Laboratory, Pasadena, CA 91109 (e-mail: bruce.banerdt@jpl.nasa.gov, thomas.c.duxbury@jpl.nasa.gov, Matthew.P.Golombek@jpl.nasa.gov, anton@gps.caltech.edu)
- P. G. Ford, G. H. Pettengill, Center for Space Research, Massachusetts Institute of Technology, Building 37, 77 Massachusetts Avenue, Cambridge, MA 02139-4307 (e-mail: pgf@space.mit.edu, ghp@space.mit.edu)
- J. B. Garvin, Office of Space Science, NASA Headquarters, Washington, DC (e-mail: garvin@denali.gsfc.nasa.gov)
- J. W. Head, Department of Geological Sciences, Box 1846, Brown University, Providence, RI 02912 (e-mail: James.Head@brown.edu)
- P. J. McGovern, Lunar and Planetary Institute, 3600 Bay Area Boulevard, Houston, TX 77058 (e-mail: mcgovern@lpi.usra.edu)
- D. O. Muhleman, Division of Geological and Planetary Sciences, California Institute of Technology, Pasadena, CA 91125 (e-mail: dom@helene.gps.caltech.edu)
- R. J. Phillips, Department of Earth and Planetary Sciences, Washington University, St. Louis, MO 63130 (e-mail: phillips@wustite.wustl.edu)
- C. L. Johnson, S. C. Solomon, Department of Terrestrial Magnetism, Carnegie Institution of Washington, 5241 Broad Branch Road, N.W., Washington, DC 20015 (e-mail: cjohnson@clrs1.ciw.edu, scs@dtm.ciw.edu)
- H. J. Zwally, Laboratory for Hydrospheric Processes, Code 970, NASA/Goddard Space Flight Center, Greenbelt, MD 20771 (e-mail: jay.zwally@gsfc.nasa.gov)

Received August 16, 2000; revised February 15, 2001; accepted February 16, 2001.

This preprint was prepared with AGU's L^AT_EX macros v5.01, with the extension package 'AGU++' by P. W. Daly, version 1.6a from 1999/05/21.